

SURVEY & REMONUMENTATION

APR 28 1995

C152256

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 14 AM 10:54

MACOMB COUNTY
REGISTERED
DEEDS
CLERK
LANSING, MI

LIBER 6527 PAGE 833

Register of Deeds Stamp & File Number

or corners in
MACOMB
(County)

Located In: Sterling Township Corner Code # H-3

Public Land Survey T 2N R 12E _____
T _____ R _____
T _____ R _____
T _____ R _____

Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Lot No. _____, Recorded Plat _____
Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | ● | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Randy Kolehouse in a field survey on September 9, 19 94

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

-3 1817 G.L.O. Notes Wampler NA Post
No other record of corner found.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-3 Set point at mid point between SE and SW corner of Section 3, using a line from the SE corner of Section 3 and an iron in Monument Box at the center line intersection of 19 Mile Road and Clinton River Road extended West. This point falls in the remains of an old fence running East & West. Fnd. 3/4" Iron Pipe 154.44 East & 0.5 North.

Measure E 2634.22 to I-3 (G.L.O. 2640)
Measure W 2634.22 to G-3 (G.L.O. 2640)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-3 I placed a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854."

PK & Macomb Co. Remon. Tag in NE Root 24" Walnut N 30° W 1.59'
PK & Macomb Co. Remon. Tag in E Face 12" Oak N 05° W 40.08'
PK & Macomb Co. Remon. Tag in SE Face 15" Walnut N 53° E 40.93'
PK & Macomb Co. Remon. Tag in NE Face 15" Ash S 51° E 43.65'
3/4" Iron Pipe E 154.44'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse
25854

Date 10/14/94

Surveyor's Michigan License No. _____

