

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

B997865  
 93 DEC 22 AM 9:02

CARMELLA SABAUGH  
 REGISTER OF DEEDS  
 MACOMB COUNTY, MI

For corners in

MACOMB

(County)

Located In:

Corner Code #

STERLING TWP.

- |                                       |                          |            |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey                 | T <u>2N</u> R <u>12E</u> | <u>1-5</u> |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                          |            |
| 5. Private Claims _____               |                          |            |

LIBER **06161PG215**

Register of Deeds Stamp & File Number

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 23, 19 93,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post, NO WITS. REMAIN

LCRC (1988) L4366, P313-BRASS CAP/MON  
 PK W FACE UTIL POLE, NORTH, 40.88'  
 PK N FACE 10" ASH, EAST, 37.42'  
 PK N FACE 10" ELM, WEST, 47.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND BRASS CAP IN STEEL ENCASED CONCRETE MON.

FOUND AND VERIFIED TWO OF THE ABOVE WITNESSES

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-1-93

*Frank J. DeDecker*  
 FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

USED FOUND CONCRETE MON.  
 WITNESSES

FND PK&T W FACE P POLE, N10E, 40.88'  
 FND PK RECESSED IN N FACE 10" ASH, SET NEW PK&MC TAG ABOVE OLD NAIL, S80E, 37.47'  
 SET PK & MC TAG E FACE OAK, SOUTH, 21.97'  
 SET PK & MC TAG S FACE 10" OAK, N85W, 12.07'



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff Date 12-9-93

Surveyor's Michigan License No. 25826