

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

B997863

For corners in

MACOMB

(County)

Located In:

Corner Code #/

STERLING TWP.

1. Public Land Survey

T 2N R 12E

K-1

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

LIBER **06161PG218**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **BRUCE ANTCLIFF**, in a field survey on **NOVEMBER 22**, 19 **93**,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post, NO WITS. REMAIN

LCRC (1986) L4353,P441, -1/2" BAR IN MON BOX
 NW BOLT SIGN POST BASE, SE, 98.66'
 SE BOLT SIGN POST BASE, SW, 108.37'
 MCRC N&T SE FACE GUY POLE, NE, 62.29'
 CONC NAIL NW FACE U.P., NW, 68.23'

MDOT(1990) 1/2" REBAR & CAP IN MON BOX
 NW BOLT MARATHON SIGN, S45E, 90.39'
 MDOT N&T IN UTIL POLE, N35E, 64.91'
 MDOT N&T IN UTIL POLE, N30W, 66.66'
 MDOT N&T IN UTIL POLE, N45W, 72.29'
 MDOT N&T IN UTIL POLE, S25W, 68.54'

MDOT & LCRC(1974) L2500,P802- 1" ROD IN MON BOX
 PP, S30W, 66.98'
 PP, N20W, 66.70'
 TEL. POLE, N30E, 82.50'

LCRC (1974) L2501,P413-1" IRON IN MON BOX
 RR SPIKE IN POLE, N26W, 66.00'
 PK IN PP, N24E, 92.10'
 PK IN POLE, S26W, 66.70'

LCRC (1989) L4828,P156, -FORM PIN
 "X" NW BOLT MARATHON SIGN, SE, 90.31'
 MDOT N&T SE FACE UTIL POLE, NE, 64.80'
 MDOT N&T SW FACE UTIL POLE, NW, 66.51'
 N&T #46304 S FACE UTIL POLE, WNW, 72.29'
 N&T #19005 NW FACE UTIL POLE, SW, 68.51'

ACCORDING TO GLO RECORDS AND
 SUBSEQUENT PLAT AND SURVEY RECORDS,
 THIS CORNER IS COMMON TO BOTH
 T2N, R12E & T3N, R12E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REBAR/MON. BOX

FOUND AND VERIFIED TWO OF THE ABOVE WITNESSES

VERIFIED MDOT DISTANCE SOUTH TO K-2 (NOW A PROPERTY CONTROLLING CORNER)

93 DEC 22 AM 9: 03

CARMELLA SABAUGH
 REGISTER OF DEEDS
 MACOMB COUNTY, MI


**ACCEPTED BY THE MACOMB COUNTY
 SURVEY PEER GROUP AS THE OFFICIAL
 CORNER UNDER MICHIGAN PUBLIC ACT 34
 OF 1990 AT A MEETING HELD ON
 12-1-93**

Frank J. DeDecker
FRANK J. DeDECKER, P.S., P.E., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

SET MACOMB COUNTY REMONUMENTATION MARKER AND CAP #25826 IN EXIST. MON. BOX.
 WITNESSES

FND PK SW FACE UTILITY POLE, N45W, 72.95
 FND MDOT N&T IN SE FACE UTILITY POLE, N38E, 64.84
 FND "X" NW BOLT MARATHON SIGN, S43E, 103.53
 SET N&T PK & MC TAG IN W FACE G. POLE, S15W, 59.91
 FND MDOT N&T SW FACE UTILITY POLE, N25W, 66.65



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff

Date 12-9-93

Surveyor's Michigan License No. 25826