

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

B997869

For corners in

<u>MACOMB</u> <small>(County)</small>	Located In: <u>STERLING TWP.</u>	Corner Code # <u>K-2</u>
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **06161 PG 219**

**Register of Deeds Stamp & File Number**

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- GLO-Post, NO WITS. REMAIN  
 LCRC (1977) L2886, P442-1/2" RE-ROD  
 PK IN 18" TREE, ELY, 103.02'  
 PK IN 18" TREE, NWLY, 156.43'  
 PK IN TAR JOINT OF PAV'T, SWLY, 72.63'
- MCRC-IRON  
 MBT, NW, 46.0'  
 14" SYCAMORE, NE, 28.0'  
 MBT, SW, 93.6'  
 IRON FENCE POST, WEST, 22.4'
- LCRC (1979) L3138, P839-1/2" PIPE W/PK/MON BOX  
 SIGN POST, S82W, 75.2'  
 NE BOLT ON LIGHT POLE, S02W, 36.3'  
 SIGN POST, S28E, 44.4'
- MDOT & LCRC (1974) L2500, P804-T IRON  
 30" MAPLE, N15W, 64.51'  
 POWER POLE, S80E, 32.36'  
 12" MAPLE, N55E, 83.85'

- MDOT (1990)-PK IN 1/2" PIPE/MON BOX  
 NE BOLT ON LIGHT POLE, SOUTH, 36.30'  
 PK IN CENTER BACK CURB N55W, 43.95'  
 PK IN CENTER BACK CURB, S45W, 51.59'  
 PK IN CENTER BACK CURB, S35E, 36.59'  
 PK IN CENTER BACK CURB, N50E, 32.38'  
 MDOT N&T IN 24" ASH, EAST, 103.41'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

FOUND PK IN 1/2" PIPE/MON. BOX  
 COR. IS IN MEDIAN APPROX. OPPOSITE THE N SIDE OF KOHL'S DEPT. STORE

THIS CORNER HAS BEEN USED AS K-2 AT LEAST SINCE 1974. HOWEVER, THE LOCATION MONUMENTED IS 676.94' NORTH OF THE PROPORTIONED LOCATION FOR THE CORNER. I SET K-2 AT THE PROPORTIONED LOCATION AND REFERENCED THIS CORNER AS A PROPERTY CONTROLLING CORNER.

SET K-2 AT PROPORTIONED DISTANCE BETWEEN K-1 & K-3, ON LINE BETWEEN FOUND K-2 (PROPERTY CONTROLLING CORNER) AND K-3.

**C. Description of monument for corner and accessories established to perpetuate locating the position of**


SET 3/4" REBAR & MACOMB COUNTY REMONUMENTATION CAP #25826 IN MEDIAN.  
 WITNESSES  
 NEW K-2 (PROPORTIONED)

- SET PK&MC TAG TOP OF CURB, N52W, 29.47'
- SET PK&MC TAG TOP OF CURB, S63W, 29.41'
- SET PK&MC TAG TOP OF CURB, S02W, 47.26'
- SET PK&MC TAG TOP OF CURB, S48E, 42.83'
- SET PK&MC TAG TOP OF CURB, N66E, 41.31'
- CHIS. "X" SE BOLT LIGHT POLE, N06E, 66.98'

93 DEC 22 AM 9:03

CARMELLA SABAUGH  
 REGISTER OF DEEDS  
 MACOMB COUNTY, MI

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-10-93  
 Frank J. DeBecker  
 FRANK J. DEBECKER, P.S., P.E., CHAIRMAN



Signed by Bruce Antcliff

Date 12-9-93

Surveyor's Michigan License No. 25826