

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

C152264
94 DEC 14 AM 10: 54

or corners in **COMMISSION**
MACOMB
(County)

Located In: Sterling Township Corner Code #

REGISTRY OF DEEDS
MACOMB COUNTY, MI

Public Land Survey	T 2N R 12E	L-7
	T R	
	T R	
	T R	
Property Controlling in Section	S T R	
	S T R	
Miscellaneous Property in Sec.	S T R	
	S T R	

LIBER 6527 PAGE 841

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Randy Kolehouse in a field survey on June 30, 1994,
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

#	Year	G.L.O.	Notes	Wampler	NA	Post
-7	1817	G.L.O.	Notes	Wampler	NA	Post
	1974	Survey	L. 2548 P. 966	Kobs	#14097	1/2" Iron Bar
	1977	Survey	L. 2781 P. 274	Smith	#16052	1/2" Iron Bar
	1977	L.C.R.C.	L. 2781 P. 276	Smith	#16052	1/2" iron Bar
	1978	Survey	L. 3023P. 362	Smith	#16052	1/2" Iron Bar
	1988	LCRC	L. 4369P. 4	Fenn	#23505	1/2" Re-rod

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 7 Found 1/2" Rebar per above Cert. Surveys and L.C.R.C.'s.
- Survey L. 2548 P. 966
PK Nail in 12" Oak W 11.02' L.C.R.C. 4369 P. 4
PK Nail in 30" Basswood (Near a Stump) SW 6.12' PK in 14" Tree West 11.02'
PK in 12" Tree NE 8.44'
- L.C.R.C. L. 2781 P. 276
Same as Above Nail in 30" Stump SW 6.64'
- Measure W 2699.12 to K-7 (G.L.O. 2640)
Measure E 2579.12 to M-7 (Rivendell Sub. No. 2 2578.2) (G.L.O. 2640)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 7 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854."
- PK N Face 20" Oak West 11.04'
PK NW Face 30" Stump S 70° W 6.67'
" + " Center Line 4" Dia. Fence Post S 50° E 12.40'
" + " Center Line Top Nut Hydrant East 93.25'
PK NW Face 24" Poplar N 44° E 8.53'



The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

signed by *Randy J. Kolehouse* Date 10/14/94
Surveyor's Michigan License No. 25854