

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

93 DEC 22 AM 9:03  
 1997878  
 CARMELLA SABAUGH  
 REGISTER OF DEEDS  
 MACOMB COUNTY, MI

For corners in

MACOMB

(County)

Located In:

Corner Code #

STERLING TWP

- |                                    |   |           |   |            |                  |
|------------------------------------|---|-----------|---|------------|------------------|
| 1. Public Land Survey              | T | <u>2N</u> | R | <u>12E</u> | <u>M-1</u>       |
|                                    | T | _____     | R | _____      | _____            |
|                                    | T | _____     | R | _____      | _____            |
|                                    | T | _____     | R | _____      | _____            |
| 2. Property Controlling in Section | S | _____     | T | _____      | <u>Sec #1 pm</u> |
|                                    | S | _____     | T | _____      | _____            |
| 3. Miscellaneous Property in Sec.  | S | _____     | T | _____      | _____            |
|                                    | S | _____     | T | _____      | _____            |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

LIBER **06161 PG 228**

Register of Deeds Stamp & File Number

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post, NO WITS. REMAIN  
 MCRC (1934) PLACED IRON-NO WITS REMAIN  
 MDOT & LCRC (1974) L2500,P794-1" IRON/MON BOX  
 POWER POLE, N30W, 68.30'  
 POWER POLE, S25W, 91.98'  
 TEL. POLE, N25E, 61.00'

LCRC (1986) L4080,P891-1/2" BAR IN MON BOX  
 NW BOLT SIGN POST BASE, SE, 98.66'  
 SE BOLT SIGN POST BASE, SW, 108.37'  
 MCRC N&T SE FACE GUY POLE, NE, 62.29'  
 CONC. NAIL NW FACE UTIL POLE, NW, 68.23'

LCRC (1991) L5290,P290-1/2" BAR/MON BOX  
 MDOT N&T SE SIDE PP, WSW, 85.64'  
 PK SE SIDE PP, SSW, 86.53'  
 PK SW SIDE PP, NW, 96.53'  
 PK NW SIDE PP, NE, 91.80'

EDISON FIELD NOTES (1980)-MON BOX  
 NAIL IN POLE, N45E, 62.4'  
 NAIL IN POLE, N45W, 68.1'  
 NAIL IN POLE, S45W, 91.8'

LCRC (1987) L4131,P656-ROD IN MON BOX  
 N&T IN UTIL POLE, N05E, 59.47'  
 N&T IN UTIL POLE, N60E, 118.10'  
 PK IN UTIL POLE, S50E, 92.30'

MDOT (1990)-1/2" IRON IN MON BOX  
 MDOT N&T IN GUY POLE, N30E, 62.40'  
 MDOT N&T IN GUY POLE, N30W, 68.35'  
 NE BOLT SIGN BASE, S40E, 99.58'  
 MDOT N&T IN PP, S60W, 85.54'

THIS CORNER IS COMMON TO ALL FOUR TOWNSHIPS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2" BAR/MON. BOX

FOUND AND VERIFIED ONE OF THE ABOVE WITNESSES

C. Description of monument for corner and accessories established to perpetuate locating the position of  
 SET MACOMB COUNTY REMONUMENTATION MARKER AND CAP #25826 IN EXIST. MON. BOX.  
 WITNESSES

FND NE BOLT SIGN BASE, S47E, 99.57'  
 SET N&T - PK & MC TAG IN SE FACE P POLE, S57W, 85.85'  
 SET N&T - PK & MC TAG IN SW FACE P POLE, N44W, 83.59'  
 SET N&T - PK & MC TAG IN N FACE P POLE, S68E, 149.67'

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff  
 Surveyor's Michigan License No. 25826

Date 12-9-93

