

# SURVEY & REMONUMENTATION

APR 28 1995

## COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

C152270

94 DEC 14 AM 10:54

CORN  
REGISTER  
MACOMB  
COUNTY, MI

LIBER 6527 PAGE 847

Register of Deeds Stamp & File Number

or corners in

MACOMB (County)

Located In: Sterling Township Corner Code ##

Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>M-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Randy Kolehouse, in a field survey on July 14, 1994,  
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

#	Date	G.L.O.	Notes	Wampler	NA	Post
1-7	1817	G.L.O.				
	1972	L.C.R.C.	L. 2302 P. 145, 146	Brabant	#17611	1/2" Iron Bar
	1972	Cert. Survey	L. 2351 P. 320	Avey	#15396	5/8" Sq. Bar
	1976	L.C.R.C.	L. 2902 P. 558	Soderberg	#17635	1" Sq. Bar
	1977	Cert. Survey	L. 2865 P. 247, 249 and L. 2886 P. 965	Avey	#15396	5/8" Sq. Bar
	1978	L.C.R.C.	L. 3106 P. 714	Soderberg	#17635	5/8" Sq. Bar
	1984	M.C.R.C.	Field Notes			1" Steel Rod
	1991	L.C.R.C.	L. 5509 P. 445	Patterson	#17631	3/4" Iron

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1-7 Found 5/8" square rod at center line Hays and 17 Mile Road. L.C.R.C. L. 2302 P. 145 SW Cor. of E. Headwell NE 35.95' Cert. Survey L. 2351 P. 320 PK with Washer ENE Face Util. Pole NW 117.39' Center Line Hole in Gatewell NE 76.21' Center Line Top Nut Fire Hyd. NE 88.60'	L.C.R.C. L. 3106 P. 714 PK with Washer in Util. Pole NW 117.39' Center Line Gate Valve NE 76.21' Center Line Fire Hyd. NE 88.60' MCRC Field Notes PK in W Face UP SW 180.36' PK in SW Face UP NW 117.20'	L.C.R.C. L. 2902 P. 558 PK in W Face UP NW 117.35' PK in S Face UP NE 35.37' PK in W Face UP SW 180.36' L.C.R.C. L. 5509 P. 445 Center Line Hyd. W 42.48'
---	--	--

Measure N. 2672.5 to A-6 (Survey L. 2302 P. 144 = 26731.1) (G.L.O. 2640)  
 Measure S. 2701.00 to A-8 (G.L.O. 2640)  
 Measure E. 2641.00 to B-7 T2N R13E (Cranberry Estates Sub = 2640.65)  
 Measure W. 2579.15 to L-7 (G.L.O. 2640)  
 This corner location is common with A-7 T2N R13E.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-7 I replaced the found 5/8" Square Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854," also set Monument Box.

PK S Face Util. Pole N 56° E 35.37'  
 Center Line Top Nut Fire Hyd. N 63° E 88.47'  
 PK W Face Util. Pole S 17° W 180.29'  
 PK with Tag "GW #78157" NW Face Util. Pole SW 44° W 46.87'  
 "+" Top Nut Fire Hyd. N 78° W 42.50'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Witnessed by Randy J. Kolehouse Date 10/14/94  
 Surveyor's Michigan License No. 25854

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 8-30-94  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

