

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in APR 28 1995

MACOMB COMMISSION Located In: STERLING TWP. Corner Code # _____
 (County)

- | | | |
|---------------------------------------|--------------------------|-----------------|
| 1. Public Land Survey | T <u>2N</u> R <u>12E</u> | <u>M-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>Sec. # 2</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEVEN E. DUNN, in a field survey on DECEMBER 2 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12/13/94

William E. Sodeberg
 WILLIAM E. SODEBERG, P.S., CHAIRMAN

A. Description of original monument and accessories and/or subsequent restoration:
 GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND
 GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

<u>L.C.R.C.</u>	<u>NAME AND NUMBER</u>	<u>DESCRIPTION</u>	<u>DATE</u>
L. 2505 P. 362	ROBERT J. PATTERSON, #17631	FOUND 1/2" IRON	JUNE 10, 1974
L. 2882 P. 384	JOHN R. FENN, #23605	FOUND PK NAIL	NOVEMBER 21, 1977
L. 5292 P. 724	ROBERT J. PATTERSON, #17631	FOUND IRON BAR IN HANDHOLE	JANUARY 7, 1992
L. 5304 P. 557	CHRISTOPHER W. NEWMAN, #24607	FOUND 1" BAR IN MONUMENT BOX	JANUARY 21, 1992

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 M-11 SECTION CORNER COMMON TO SEC. 30, T.2N., R.13E., CLINTON TWP.

FOUND 1" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT
 VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF L.C.R.C.'S AS LISTED BELOW AND DISTANCE FROM A-11 TO A-12 AS SHOWN ON "FRASER TECHNOLOGY CENTER NO. 1" AS RECORDED IN LIBER 93 OF PLATS ON PAGES 1 THRU 4 (M.C.R.)

FOUND WITNESSES

L. 5292 P. 724	S.40°E. 72.57'	SET PK NAIL IN UTILITY POLE
	S.35°W. 59.49'	FOUND PK NAIL IN UTILITY POLE
L. 5304 P. 557	S.45°E. 72.45'	POWER POLE

FIELD MEASUREMENTS AND RECORDED DISTANCES
 M-11 TO B-11 (CLINTON TWP.) 2635.56' (M.) 39.94 (GLO) 2636.04'
 M-11 TO M-12 2666.01' (M.) 2666.05' (R.) "FRASER TECHNOLOGY CENTER NO. 1"

C. Description of monument for corner and accessories established to perpetuate locating the position of the

M-11 T.2N., R.12E. I REPLACED 1" IRON ROD WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN AN EXISTING MONUMENT BOX.

WITNESSES

S.38°W. 59.53'	FOUND FORM NAIL AND TAG #30103 IN NORTH SIDE OF UTILITY POLE
S.40°E. 72.52'	FOUND FORM NAIL AND TAG #30103 IN SOUTHWEST SIDE OF UTILITY POLE
S.40°E. 72.48'	FOUND PK NAIL IN SOUTHWEST SIDE OF UTILITY POLE
S.65°E. 87.26'	CENTER TOP NUT OF FIRE HYDRANT
N.43°E. 72.46'	SCRIBED "+" ON WEST RIM OF MBT MANHOLE
N.35°W. 59.15'	SCRIBED "+" ON SOUTH RIM OF GAS VALVE

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn Date Dec. 20, 1994
 Surveyor's Michigan License No. 28408

