


APR 29 1996

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corner **COMMISSION**

<u>MACOMB</u> (County)	Located In: <u>Sterling Twp.</u>	Corner Code # <u>K-1</u>
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>K-1</u>
	T <u>   </u> R <u>   </u>	<u>SEQ 2 W</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-15-95  
  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, George M. Platz, in a field survey on August 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-1 T.2N.,R.12E. G.L.O. Notes Pg. 379 Joseph Wampler 1817 Intersected Twp. Line at Post
- Note: All Records Indicate that this Corner is Common to Both T.2N.,R.12E. & T.3N.,R.12E.
- K-1 T.2N.,R.12E. LCRC Liber 2500, Pg. 800 N.C. Jones 1974 1" Iron in Mon. Box
- K-13 T.3N.,R.12E. LCRC Liber 2501, Pg. 413 William Carlson 1974 1" Iron in Mon. Box
- K-1 T.2N.,R.12E. LCRC Liber 4353, Pg. 441 Herbert Avey 1986 Fd. 1/2" Iron in Mon. Box
- K-1 T.2N.,R.12E. LCRC Liber 4828, Pg. 156 Shelby Money 1989 Fd. Form Pin
- K-1 T.2N.,R.12E. LCRC MDOT Witness Card 1990 1/2" Iron in Mon.Box
- K-1 T.2N.,R.12E. LCRC Liber 6161, Pg. 218 Bruce Antcliff 1993 Set 3/4" Iron w/ Remon Cap
- K-13 T.3N.,R.12E. LCRC Liber 6161, Pg. 234 Bruce Antcliff 1993 Set 3/4" Iron w/ Remon Cap

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-1 Set 3/4" Iron Rod with Aluminum Disk Stamped "Macomb County Monument, MI Act 345, #38121" in Location that was Accepted by the Macomb County Remonumentation Peer Group in 1993. Bruce Antcliff, PS #25826, performed the Remonumentation Survey in 1993. The Corner was destroyed in the Spring of 1994 when M-59 was widened. Prior to its destruction, the point was witnessed by Spalding DeDecker & Associates and upon completion of the paving, the point was reset in the same position that was accepted by the Macomb County Remonumentation Peer Group in 1993.
- This point falls 2651.4' West of the N.1/4 Cor. of Section 1, Sterling Twp. T.2N.,R.12E.
- This point falls 2654.2' East of the N.1/4 Cor. of Section 2, Sterling Twp. T.2N.,R.12E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 Northeast Corner of Section 2, Sterling Twp. T.2N.,R.12E. Set 3/4" Iron Rod with Aluminum Disk Stamped "Macomb County Monument, MI Act 345, #38121" in Monument Box located near the Intersection of Schoenherr Road and East Bound M-59.
- Az. 54° 61.28'; Set Chiseled "+" in the Base Plate of a Steel Traffic Signal Pole
- Az. 126° 75.12'; Set Chiseled "+" in the NW Corner of a Square Catch Basin
- Az. 212° 65.93'; Set Chiseled "+" in the Base Plate of a Steel Traffic Signal Pole
- Az. 344° 113.98'; Set P.K. Nail w/Macomb County Witness Tag in West Face of a Utility Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by George M. Platz Date 9-12-95  
 Surveyor's Michigan License No. 38121

