

**SURVEY & REMONUMENTATION**

APR 28 1995

C152207

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

4 corners in  
MACOMB  
 (County)

Located In: Clinton Township Corner Code ##

Public Land Survey	T <u>2N</u> R <u>13E</u>	<u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

LIBER **6527** PAGE **784**

94 DEC 14 AM 10:51

CLIFF BAUGH  
 CLERK OF DEEDS  
 MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Randy Kolehouse in a field survey on July 15, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

4	1817	G.L.O.	Notes	Wampler	N/A	Post
	1934	MCRC	Files	N/A	N/A	1" Solid Iron
	1972	Cert. Survey	L. 2314 P. 234	Avey	#15396	3/4" Pipe
	1973	L.C.R.C.	L. 2464 P. 470	South	#20623	1" Pipe
	1977	Cert. Survey	L. 2772 P. 460-465	Smith	#16052	1" Pipe
	1978	Cert. Survey	L. 2936 P. 775	Smith	#16052	1" Pipe
	1979	L.C.R.C.	L. 3184 P. 577	Fenn	#23505	1" Pipe
	?	MCRC	Files	N/A	N/A	Pipe

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 4 Found 1" pipe in center line of Hayes Road.  
 L.C.R.C. L. 2464 P. 470  
 SE Cor. Brick House #42109 NW 150.69'  
 NE Cor. House #42071 WSW 90.69'  
 SW Cor. House #42100 NE 99.39'  
 Cert. Survey L. 2314 P. 234  
 16D Cone Nail NE Face Util. Pole NW 108.85'
- L.C.R.C. L. 4718 P. 611  
 SW Cor. House #42100 ENE 99.26'  
 SE Cor. House #42109 NW 150.62'  
 NW Cor. Building (Vinnie's) ENE 138.40'  
 SE Cor. House #42087 WNW 123.04'
- L.C.R.C. L. 3184 P. 577  
 Nail in Util. Pole NW 108.95'
- Measure N. 2706.06 to A-3 (G.L.O. 2640)  
 Measure S. 2698.47 to A-5 (G.L.O. 2640)  
 This corner location is common with M-4 T2N R12E.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 4 I replaced the found 1/2" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854," also set Monument Box.  
 SW Cor. House #42100 N 62° E 99.27'  
 NW Cor. Building "Vinnie's" S 72° E 138.47'  
 SE Cor. House #42087 N 85° W 122.96'  
 SE Cor. House #42109 N 43° W 150.61'  
 Conc. Nail NE Face P. Pole N 19° W 108.88'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Recorded by Randy J. Kolehouse Date 10/14/94  
 Surveyor's Michigan License No. 25854

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 8-16-94  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

