

SURVEY & REMONUMENTATION

APR 28 1995

C152209

COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

corners in
MACOMB
(County)

Located In: Clinton Township Corner Code #

Public Land Survey	T <u>2N</u> R <u>13E</u>	<u>A-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
Miscellaneous	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

LIBER **6527** PAGE **786**

94 DEC 14 AM 10:51
REGISTER OF DEEDS
MACOMB COUNTY, MI
Register of Deeds Stamp & File Number

Lot No. , Recorded Plat
Private Claims

Randy Kolehouse in a field survey on July 15, 19 94, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

6	1817	G.L.O.	Notes	Wampler	NA	Post
	1972	L.C.R.C.	L. 2302 P. 145, 146	Brabant	#17611	1/2" Bar
	1972	Survey	L. 2302 P. 144	Brabant	#17611	
	1977	Cert. Survey	L. 2761 P. 470	Smith	#16052	Iron
	1977	L.C.R.C.	L. 2918 P. 56	Patterson	#17631	1/2" Iron
	1977	Cert. Survey	L. 2865 P. 247	Avey	#15396	1/2" Bar
			L. 2886 P. 965			
	1978	L.C.R.C.	L. 2902 P. 559	Soderberg	#17635	1" Iron Pipe
	1978	L.C.R.C.	L. 3059 P. 199	Soderberg	#17635	1/2" Re-Rod
	1989	L.C.R.C.	L. 4799 P. 506	Donnelly	#21563	1/2" Rod

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6 Found 1/2" rebar in center line of Hayes Rd. and Stadler Road.

L.C.R.C. L. 2918 P. 56 Nail and Washer Util. Pole ESE 59.18' Nail and Washer Util. Pole NW 57.62'	L.C.R.C.'s L. 2865 P. 247, 249 and L. 2886 P. 965 16D Nail and Washer NW Face Util. Pole NW 57.62' 16 D. Nail and Washer S Face Util. Pole E 59.13'	L.C.R.C. L. 3059 P. 199 PK NE Face DE Pole NW 57.46' Nail S Face DE Pole E 59.24'
---	---	---

L.C.R.C. L. 2902 P. 559 Nail and Washer N Face Util. Pole NW 57.64' Nail and Washer S Face Util. Pole E 59.23'	L.C.R.C. L. 4799 P. 506 PK with Tag S Face Util. Pole ESE 59.20' Center Line Top Nut Hyd. NW 73.68'
--	---

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-16-94


William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Measure N. 2695.56 to A-5.
Measure S. 2672.50 to A-7 (Survey L. 2302 P. 144 = 2673.1) (G.L.O. 2640)
This corner location is common with M-6 T2N R12E.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3 I replaced the found 1/2" Rebar with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854," also set Monument Box.

PK with Tag #21563 S Face Util. Pole S 80° E 59.22'
PK & Macomb Co. Remon. Tag in NW Face Util. Pole S 24° W 134.03'
PK NE Face Util. Pole N 47° W 58.73'
Center Line Top Nut Fire Hyd. N 27° W 73.81'



The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Recorded by Randy J. Kolehouse Date 10/14/94
Surveyor's Michigan License No. 25854