

**SURVEY &  
REMONUMENTATION**

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

C152212

LIBER 6527 PAGE 789

For corners in **COMMISSION**  
**MACOMB**  
(County)

Located In: **Clinton** Corner Code **##**  
**Township**

- |                                       |                          |            |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey                 | T <u>2N</u> R <u>13E</u> | <u>A-9</u> |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                          |            |
| 5. Private Claims _____               |                          |            |

94 DEC 14 AM 10:51  
REGISTERED  
DEEDS  
CLINTON TWP. MI

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on September 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-9	1817	G.L.O.	Notes	Wampler	NA	Post
	1982	A.E.W.	Notes	SWM/RF	NA	1/2" Rebar w/Cap #17635

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9 Found 1/2" rebar w/cap #17635 in field southwesterly of Utica Road and North of Red Run Drain as set by Anderson, Eckstein, & Westrick.

AEW Notes

Nail w/tag #123 NE Face Util. Pole N 19° W 77.28'  
SE Cor. Flange at SE Cor. D.E. Tower #5115 N 4° SE 496.28'  
SW Cor. Block Building #37194 N 3° E 562.34'  
C/L Top Hyd. N Side Utica Rd. 150' ± West of N 36° E 470.94' Red Run Drain

Measure North to A-8 = 2641.87' (A.E.W. 2642.92') (G.L.O. 2640)  
Measure East to B-9 T2N R13E = 2720.04' (Monterey Sub. 2725.30') (G.L.O. 2640)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-4-94  
William E. Soderberg  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854."

Nail with Tag #123 NE Face Util. Pole N 12° W 77.28'  
SE Cor. SE Leg (at Ground Level) D.E. Tower #5115 N 69° E 496.13'  
SW Cor. Block Building #37194 N 27° E 562.28'  
C/L Top Bolt Hyd. N'y Side Utica Road N 61° E 470.81'  
Chiseled "+" SW Bolt for Railing at SW Cor. Bridge for Utica Road over Red Run Drain N 73° E 341.94'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 10/14/94  
Surveyor's Michigan License No. 25854

