

**SURVEY &
REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FEB 27 1997

For corners in

<u>MACOMB</u> (County)	Located In: Clinton Twp	Corner Code # <u>B3</u>
1. Public Land Survey	T <u>2N</u> R <u>13E</u>	<u>B3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Sept 2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

COMMISSION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-22-96
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Craig P. Amey, in a field survey on May 24, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1817	William Preston	Set post	GLO
none	George Avedt #16034	Set 1/2" iron	Unrecorded Survey
1972	Herbert Kobs #14097	Found 1/2" iron bar	LCRC L2279 P374
1973	David South #20623	Found #4 rebar	LCRC L2464 P468
1979	John Fenn #23505	Found 1/2" rerod in mon box	LCRC L3184 P577
1982	Detroit Edison	Set 1/2" pin in mon box	Notes
1989	Martin Dunn #30081	Found 1/2" iron in mon box	LCRC L4687 P331
1993	Bruce Antcliff #25826	Found 1/2" rod in mon box	LCRC L6161 P238

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Macomb County Remonumentation cap and iron in a monument box at the intersection of Dalcoma Road and 19 Mile Road. The location was witnessed prior to road construction. After completion of the road construction, and resetting of the monument box, a Macomb County Remonumentation cap was set on a 3/4" x 24" iron at the prior location according to AEW witnesses and LCRC L6161 P238 witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced existing found iron with a 3/4" by 24" rebar with a 2" diameter aluminum cap stamped "Macomb County Monument MI 345 D3 34970"

0°	157.24'	Set PK nail in the centerline joint of Dalcoma Road
0°	396.86'	Set PK nail in the centerline joint of Dalcoma Road
21°	117.68'	Set 1/2" rebar with "TRAV" cap at back of walk
66°	144.30'	Set 1/2" rebar with "TRAV" cap at back of walk
139°	75.93'	Set 1/2" rebar with "TRAV" cap at back of walk
221°	74.82'	Set 1/2" rebar with "TRAV" cap at back of walk

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Craig P. Amey Date 12-9-96
Surveyor's Michigan License No. 34970