

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

CLINTON TWP.

For corners in

MACOMB (County)	Located In:	Corner Code #
1. Public Land Survey	T 2N R 13E	C-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	<u>Seg. # 2 pm</u>
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD
 ON 12-13-94

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George M. Platz, in a field survey on November 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Clinton Twp.

A. Description of original monument and accessories and/or subsequent restoration:

- C-1 T.2N.,R.13E. G.L.O. Notes Pgs. 245-249 William Preston 1818 Set Post
- C-1 T.2N.,R.13E. MCRC Witness Card 1934 Cross in Pavement
- C-1 T.2N.,R.13E. MDOT Witness Card Clifford Lindgren 1971 Found Mon. Box w/ 1" Pin
- C-1 T.2N.,R.13E. LCRC Liber 4113, Pg. 178 John Fenn 1987 Found Mon. Box w/ Iron
- C-1 T.2N.,R.13E. MDOT Witness Card Keith H. Schultz 1988 Found Mon. Box w/ 1/2" Rod
- C-1 T.2N.,R.13E. LCRC Liber 6161, Pg. 239 Bruce Antcliff 1993 Set Macomb Co. Remon. Disk

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-1 Set 3/4" Iron Rod with Aluminum Disk Stamped "Macomb County Monument, MI Act 345, #38121" in Location that was Accepted by the Macomb County Remonumentation Board in 1993. Bruce Antcliff, PS #25826, performed the Remonumentation Survey in 1993. The Corner was destroyed in the Spring of 1994 when M-59 was widened. Prior to its destruction, the point was witnessed by Spalding DeDecker & Associates and upon completion of the paving, the point was reset in the same position that was accepted by the Macomb County Remonumentation Board in 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1 Northeast Corner of Section 6 and Northwest Corner of Section 5, Clinton Twp. T.2N.,R.13E. Set 3/4" Iron Rod with Aluminum Disk Stamped "Macomb County Monument, MI Act 345, #38121" in Monument Box located in the Intersection of Garfield Rd. South and East Bound M-59 This point falls 594.9'+/- Easterly of the SW Corner of Section 32, Macomb Twp. T.3N.,R.13E.
- Az. 11° 267.41'; Set 1/2" Iron Rod w/"SDA TRAV." Cap at the Back of Curb
- Az. 63° 63.69'; Set Chiseled "+" in the West Face of a Steel Signal Pole
- Az. 140° 96.24'; Found P.K. Nail w/ "Macomb County Witness" Tag in SW Face of Utility Pole
- Az. 237° 192.35'; Set 1/2" Iron Rod w/"SDA TRAV." Cap at SE Corner of Conc. Pad to MCC Sign
- Az. 250° 118.64'; Set P.K. Nail w/Tag #38121 in SE Face of Utility Pole
- Az. 352° 114.26'; Set P.K. Nail w/Tag #38121 in East Face of Utility Pole
- Az. 359° 336.93'; Set 1/2" Iron Rod w/"SDA TRAV." Cap at NE Corner of a Concrete Headwall

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by George M. Platz Date 12-13-94

Surveyor's Michigan License No. 38121

