

# SURVEY & REMONUMENTATION

APR 28 1995

## LAND CORNER RECORDATION CERTIFICATE

C152216

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**MACOMB**

(County)

Located In: Clinton Township Corner Code ≠

1. Public Land Survey	T	<u>2N</u>	R	<u>13E</u>	<u>C-4</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

LIBER **6527** PAGE **793**  
94 DEC 14 AM 10:51  
CANTON RECORDS  
LAUGH DEEDS  
CITY, MT

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on August 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

C-4	1817	G.L.O.	Notes	Preston	NA	Post
	1972	Survey	L. 2336 P. 432	Soderberg	#17635	NA
	1973	L.C.R.C.	L. 2464 P. 474	South	#20623	#4 Rebar
	1979	Survey	L. 3106 P. 715	Soderberg	#17635	Iron
	1990	L.C.R.C.	L. 05011 P. 426	Patterson	#17631	PK
	1992	L.C.R.C.	L. 05524 P. 827	Money	#30092	Chiseled "+"

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

C-4 Found and accepted chiseled "+" in concrete roadway (Garfield Road) 144.0 North of Monument Box at center line of Canal Street. This point checks ± 0.25 the measurements shown to C-3 and C-5 in L.C.R.C. L. 2464 P. 474 (which was re-established using ties from Lehner Assoc. in 1973). The PK shown in L. 05011 P. 426 is 1.48' South.

L.C.R.C. 5524 P. 827  
"+" on N Edge M.H. Rim SE 89.67'  
PK in SE Face Util. Pole SW 74.65'  
Back Curb W 29.08'  
PK in NE Face Util. Pole NW 56.38'

Measure N 2653.07 to C-3 (L.C.R.C. 2464 P. 474 - 2652.69) (G.L.O. 2640)  
Measure S 2667.95 to C-5 (L.C.R.C. 2664 P. 474 - 2668.11) (G.L.O. 2640)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94  
*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

C-4 I placed a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854," also set Monument Box.

Center Line Nut on Hyd. N 31° E 102.53'  
"+" N Rim M.H. S 28° E 89.62'  
PK SE Face Util. Pole S 38° W 74.65'  
PK NE Face Util. Pole N 39° W 56.38'  
5/8" Rebar in Mon. Box at Center Line Canal S 143.96'  
PK S 1.48'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 10/14/94  
Surveyor's Michigan License No. 25854

