

**SURVEY &
REMONUMENTATION**

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

C152217

LIBER 6527 PAGE 794

For corners in
MACOMB
(County)

COMMISSION

Located In: **Clinton Township** Corner Code **#**

1. Public Land Survey	T	<u>2N</u>	R	<u>13E</u>	<u>C-5</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

94 DEC 14 AM 10:52

MAHON
RECORDS
CLINTON TWP. MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on August 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-5	1817	G.L.O.	Notes	Preston	NA	Post
	1959	MCRC	Rec. #63			48" Stake
	1966	Lehner & Assoc.		NA	NA	1" Rod
	1973	L.C.R.C.	L. 2464 P. 460	South	#20623	1" Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 Found 5/8" rebar in monument box at intersection of 18 Mile and Garfield Roads.

L.C.R.C. L. 2464 P. 460	Lehner Assoc. Records 1966
Center Line Top Nut Hyd. NW 80.40'	Center Line Hyd. NW 80.8'
Center Line Gate Valve and Well SW 82.37'	Center Line Valve and Wall SW 81.8'
Center Line Fire Hyd. NW 80.75'	
C-4 N. 2668.11'	
B-5 W. 2676.65'	

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Measure N 2667.95 to C-4 (L.C.R.C. L. 2464 P. 474 - 2668.11) (G.L.O. 2640)
Measure E 2726.55 to D-5 (G.L.O. 2689.5)
Measure S 2661.40 to C-6 (G.L.O. 2640)
Measure W 2676.55 to B-5 (G.L.O. 2640)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5 I replaced the found 5/8" Rebar with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing Monument Box.

Center Line Top Nut Hyd. N 29° W 80.84'
Center Line Top Nut Hyd. N 33° E 93.53'
"+ S Most Bolt "Sunoco" Gas Station Sign N 50° E 108.35'
PK Nail SW'y Face Signal Pole S 45° E 64.42'
D.H. Nail with Washer SE'y Face Util. Pole S 23° W 120.13'
Center Line Gate Valve and Well S 34° W 81.78'
"+ N'y Rim San. M.H. S 51° W 92.97'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 10/14/94

