

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

C152220
94 DEC 14 AM 10:52

CASH RECEIVED
RECORDS DEEDS
MICHIGAN DEPT. OF
NATURAL RESOURCES

For corners in
MACOMB
(County)

Located In: Clinton Township Corner Code #

1. Public Land Survey	T <u>2N</u>	R <u>13E</u>	<u>C-8</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

LIBER 6527 PAGE 797

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on Sept. 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8 1817 G.L.O. Notes Preston NA Post
No other evidence of corner on record.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-4-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 Searched for but did not find any evidence of G.L.O. corner. Set iron on the center line of Garfield Road extended from the SE corner Section 19 through the P.C. of a curve at Sta. 18+25.43 per Macomb County Road Commission Street Improvement Plans to a distance of 2668.00'. (Average of G.L.O. dist. as measured in Clinton Township) Said point falls 48.75' East of a line between the NE & SE corners of Section 19.

Measure South to C-9 = 2668.0'
Measure North to a Property Controlling Corner on North Side of Clinton River = 1217.57'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-8 I placed a 3/4" x 24" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854."
- PK & Macomb Co. Remon. Tag W Face 8" Twin Tree N 30° E 14.05'
 - PK & Macomb Co. Remon. Tag W Face 24" Poplar S 20° E 48.02'
 - PK & Macomb Co. Remon. Tag Back Curb E Side Garfield Rd. S 83° W 31.37'
 - NE Cor. C.B. at Back Curb N 77° W 32.27'
 - PK & Macomb Co. Remon. Tag W Face Guy Pole N 17° W 81.60'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 10/14/94

