

SURVEY &
REMONUMENTATION

APR 28 1995
C0158352 LIBER:06543 PAGE:374 08:35A 01/05/1995
CAMPBELL SABAUGH-MACOMB COUNTY, MI REG/DEEDS

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB

(County)

Located In:
CLINTON

Corner Code #

1. Public Land Survey

T 2N R 13E

E-12

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____

T _____ R _____

S _____

T _____ R _____

3. Miscellaneous
Property in Sec.

S _____

T _____ R _____

S _____

T _____ R _____

4. Lot No. _____, Recorded Plat

5. Private Claims _____

Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on MARCH 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3	9	8	7	6	5	4	3	2	1				
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND
GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

ACCEPTED BY THE MACOMB COUNTY SURVEY PEOP GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-13-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-12 1/4 CORNER

FOUND 1/2" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT.



FIELD MEASUREMENTS AND RECORDED DISTANCES

E-12 TO E-11 2763.78' (M.) 40.00 (GLO) 2640.00'
E-12 TO E-13 2586.80' (M.) 40.00 (GLO) 2640.00'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 T.2N., R.13E. I REPLACED 1/2" IRON ROD WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT. 345 #28408" IN AN EXISTING MONUMENT BOX.

WITNESSES

S.75°E. 37.42' FOUND PK NAIL IN NORTHEAST FACE OF UTILITY POLE
S.23°W. 94.90' FOUND PK NAIL IN EAST FACE OF UTILITY POLE
S.61°W. 85.76' CENTER TOP NUT OF FIRE HYDRANT
N.60°W. 76.56' FOUND PK NAIL IN NORTH FACE OF UTILITY POLE

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn
28408

Date Dec. 20, 1994

Surveyor's Michigan License No. _____