

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

C150803

For corners in

MACOMB

(County)

Located In:
CLINTON TWP.

Corner Code #

LIBER **6523** PAGE **950**

94 DEC -9 PM 2:50

CARROLL BAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

1. Public Land Survey T 2N R 13E F-13
T R
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
6													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, STEVEN E. DUNN, in a field survey on APRIL 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND
GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

L.C.R.C.	NAME AND NUMBER	DESCRIPTION	DATE
L. 5483 P. 426	ROGER J. STECKER, #30103	FOUND 1/2" IRON ROD IN MONUMENT BOX	JUNE 22, 1992

PLATS	NAME AND NUMBER	DATE
L. 3 P. 161	HARMON FARMS	JULY 26, 1919
L. 7 P. 97	GRATIOT MASONIC PARK	JULY 19, 1924

ACCEPTED BY THE MACOMB COUNTY SURVEY PE GROUP AS THE OFFICIAL CORNER UNDER MICHIG PUBLIC ACT 345 OF 1990 AT A MEETING HE ON 11-15-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 QUARTER CORNER COMMON TO F-1 ERINLAKE TOWNSHIP
FOUND 1/2" IRON ROD IN MONUMENT BOX IN ASPHALT PAVEMENT. VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF ABOVE L.C.R.C.'s AND M-DOT DISTANCES TO THE SECTION.

FOUND WITNESS TIES	FOUND WITNESS TIES	FOUND WITNESS TIES
L. 5483, P. 426	AZ 51° 51.91'	SQUARE HEADED NAIL IN WEST FACE OF DETROIT EDISON POLE
	AZ 330° 51.30'	PK. NAIL AND M.C.R.C. CAP IN EAST FACE OF DETROIT EDISON POLE
	AZ 231° 53.71'	PK. NAIL AND M.C.R.C. CAP IN NORTHWEST FACE OF DETROIT EDISON POLE
	AZ 138° 54.17'	FACE OF 4" STEEL WALK SIGNAL POST

FIELD MEASUREMENTS AND RECORDED DISTANCES
F-13 TO G-13 2672.53' (M.) 2672.80' "GRATIOT MASONIC PARK" (R.) L. 7, P. 97 2640.00' G.L.O. (R.)
F-13 TO E-13 2699.14' (M.) 2700.60' "HARMON FARMS" (R.) L. 3, P. 161 2640.00' G.L.O. (R.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 T.2N., R.13E. I REPLACED 1/2" IRON ROD WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN AN EXISTING MONUMENT BOX IN ASPHALT PAVEMENT.

WITNESSES

AZ 51° 51.91'	SQUARE HEADED NAIL IN WEST FACE OF DETROIT EDISON POLE
AZ 330° 51.30'	SET PK NAIL AND M.C.R. WITNESS TAG IN EAST FACE OF DETROIT EDISON POLE
AZ 231° 53.71'	PK NAIL AND M.C.R.C. CAP IN NORTHWEST FACE OF DETROIT EDISON POLE
AZ 138° 54.17'	FACE OF 4" STEEL WALK SIGNAL POST

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn Date Nov. 16, 1994

Surveyor's Michigan License No. 28408

