

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

C152230  
94 DEC 14 AM 10:52

CLERK OF THE  
REGISTRY OF DEEDS  
MACOMB COUNTY, MI

For corners in

MACOMB

(County)

Located In: Clinton Township Corner Code #

1. Public Land Survey	T <u>2N</u> R <u>13E</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **6527** PAGE **807**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on Sept. 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G-1	1817	G.L.O.	Notes	Preston	NA	Post
	1978	Cert. Survey	L. 3089 P. 916	Soderberg	#17635	N/A
	1979	Cert. Survey	L. 3263 P. 897	Soderberg	#17635	N/A
	1979	Cert Survey	L. 3263 P. 910	Soderberg	#17635	N/A
	1985	L.C.R.C.	L. 4723 P. 616	Donnelly	#21563	PK Nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found PK nail in center line of Hall Road (M-59) per L.C.R.C. L. 4723 P. 616 checks 580.1 East of G-13 T3N R13E (G.L.O. 574.0) checks dist. to I-13 T3N R13E as shown in Cert. Survey L. 3263 P. 897 (R = 4784.7 M 4785.0). Also checks following witness ±.

L.C.R.C. L. 4723 P. 616

PK in Util. Pole S 60° E 103.11'  
PK in Util. Pole S 35° W 75.04'

Measure W 2669.6 to F-1 (G.L.O. 2640)  
Measure E 2679.45 to H-1 (G.L.O. 2640)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-4-94

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 I replaced the found PK nail with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854," also set Monument Box.

PK & Macomb Co. Remon. Tag in W Face P. Pole S 54.25'  
PK & Macomb Co. Remon. Tag in NW Face P. Pole S 49° W 75.04'  
PK & MDOT Tag in NW Face P. Pole S 54° E 103.11'  
C/L Top Nut Hyd. S 59° W 82.88'  
C/L Sign Post N 23° E 35.54'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse  
25854

Date 10/14/94

Surveyor's Michigan License No. \_\_\_\_\_

