

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C150804

For corners in

MACOMB

(County)

Located In: CLINTON TWP.

Corner Code #

LIBER 6523 PAGE 951

94 DEC -9 PM 2:50

CARYL A. BAUGH
REGISTERED CLERK OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 2N R 13E G-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 6-36.

I, STEVEN E. DUNN, in a field survey on APRIL 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules; therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND
GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

Table with columns: L.C.R.C., NAME AND NUMBER, DESCRIPTION, DATE. Lists survey points and dates.

Table with columns: PLATS, NAME AND NUMBER, DATE. Lists Gratiot Masonic Park.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 SECTION CORNER COMMON TO G-1 ERINLAKE TOWNSHIP
FOUND REROD IN MONUMENT BOX IN CONCRETE PAVEMENT. VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF ABOVE L.C.R.C.'s AND COMPARED M-DOT DISTANCES TO THE SECTION CORNERS TO THE EAST AND WEST.

Table with columns: FOUND WITNESSES, DISTANCE, DESCRIPTION. Lists witness points and utility pole locations.

FIELD MEASUREMENTS AND RECORDED DISTANCES
G-13 TO F-13 2672.53' (M) 2672.80' "GRATIOT MASONIC PARK" (R) L.7, P. 47 2640.00' G.L.O. (R)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 T.3N., R.13E. I REPLACED 1/2" IRON ROD WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN AN EXISTING MONUMENT BOX.

Table with columns: WITNESSES, DISTANCE, DESCRIPTION. Lists witness points and utility pole locations.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn Date Nov 16, 1994

Surveyor's Michigan License No. 28408

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-15-94
WILLIAM E. SODERBERG, P.S., CHAIRMAN

