

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C152232

94 DEC 14 AM 10: 52

For corners in

MACOMB

(County)

Located In: **Clinton Township**

Corner Code #

CAL. REG. DEEDS LAUGH COUNTY, MI

- 1. Public Land Survey T 2N R 13E I-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

LIBER 6527 PAGE 809

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on Sept. 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1	1817	G.L.O.	Notes	Wampler	NA	Post
	1938	MDOT	Road Plan			1 1/2" Iron Bar
	1972	Cert. Survey	L. 2295 P. 438	Smith	#16052	1" Pin
	1972	L.C.R.C.	L. 2302 P. 900	Smith	#16052	1" Pin
	1988	MDOT	Wit. Card	Gorman	#17622	Iron in Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Iron as found and recorded in L. 2295 P. 438 and L. 2302 P. 900 is also recorded as I-13 T3N R13E in L. 3179 P. 740 by Wm. Soderberg and has been remonumented as I-13 T3N R13W in 1994. After reviewing MDOT Road Plans from 1938 to present and measurements along Town line from E-1 to L-1, I feel the point as recorded in L. 2302 P. 900 is actually I-13 T3N R13E. Set point at Gov. Dist. 574.2 East of I-13 for Section corner. On line between I-13/J-13 T3N R13E. (MDOT = 571.0 ± per Road Plans 1938)

Measure W 2679.45' to H-1 (G.L.O. 2640)
Measure E 2697.80 to J-1 (G.L.O. 2640)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-4-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 I placed a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing Monument Box.

- PK & Macomb Co. Remon. Tag in W Face 10" Elm N 14° E 30.58'
- PK & Macomb Co. Remon. Tag in NW Face P. Pole S 57° W 198.40
- PK & Macomb Co. Remon. Tag W in P. Pole S 11° W 147.02'
- PK & Macomb Co. Remon. Tag in W Face P. Pole S 10° E 161.59
- Fnd. PK in NE Face MBT Pole N 47° W 41.44'
- North Edge of Hall Road (M-59) Pavement South 75.9'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J Kolehouse
Surveyor's Michigan License No. 25854

Date 10/14/94

