

LIBER 061667082

B999695

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)

Located In: SHELBY TOWNSHIP Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 AM

DEC 28 1993

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-2-N R-13-E M-4
2. Property Controlling in Section S-T-R
3. Miscellaneous Property in Sec. S-T-R

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (4,12) is marked with a dot.

I, DAVID PAWLACZYK in a field survey on NOVEMBER 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A POST WAS SET PER GOVERNMENT LAND OFFICE RECORDS, N. 52° E. 18 LINKS 16" ELM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" RE-ROD PREVIOUS LAND CORNER RECORDATION CERTIFICATE LIBER 3021 PAGE 208 LIBER 4479 PAGE 89

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 1/2" RE-ROD WITH P.A. 345 ALUMINUM CAP STAMPED #17632 ON A 3/4" X 24" IRON ROD. ACCESSORIES ESTABLISHED

N. 30° E. 68.23' WITNESS TAG IN 24" MAPLE
N. 60° E. 118.98' S.W. CORNER BLOCK PUMP HOUSE
S. 20° E. 170.96' WITNESS TAG IN UTILITY POLE
WEST 20.03' WITNESS TAG IN UTILITY POLE
SOUTH 132.00' WEST 1/4 CORNER SECTION 7 MACOMB

Signed by [Signature] Surveyor's Michigan License No. 17632

Date 12-20-93

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93

[Signature] FRANK J. DeDECKER, PS, PE, CHAIRMAN

