

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLINTON TWP

| | | |
|------------------------------------|---|--------------------|
| <u>MACOMB</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 2N R 13E | E-1 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | <i>leg. # 2 jm</i> |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. _____, Recorded Plat | ON <u>12-13-94</u> | |
| 5. Private Claims | <u>William E. Soderberg</u> WILLIAM E. SODERBERG, P.S., CHAIRMAN | |

Register of Deeds Stamp & File Number

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-13-94

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, George M. Platz, in a field survey on November 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Clinton Twp.

A. Description of original monument and accessories and/or subsequent restoration:

- E-1 T.2N.,R.13E. G.L.O. Notes Pgs. 245-249 William Preston 1818 Set Post
- E-1 T.2N.,R.13E. LCRC Liber 3059, Pg 203 William Soderberg 1979 Found Mon. Box w/1" Rerod
- E-1 T.2N.,R.13E. MDOT Witness Card Don Gorman 1988 Found Mon. Box w/1" Rerod
- E-1 T.2N.,R.13E. LCRC Liber 6161, Pg 243 Bruce Antcliff 1993 Set Macomb Co. Remon. Disk

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 Set 3/4" Iron Rod with Aluminum Disk Stamped "Macomb County Monument, MI Act 345, #38121" in Location that was Accepted by the Macomb County Remonumentation Board in 1993. Bruce Antcliff, PS #25826, performed the Remonumentation Survey in 1993. The Corner was destroyed in the Spring of 1994 when M-59 was widened. Prior to its destruction, the point was witnessed by Spalding DeDecker & Associates and upon completion of the paving, the point was reset in the same position that was accepted by the Macomb County Remonumentation Board in 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Northeast Corner of Section 5 and Northwest Corner of Section 4, Clinton Twp. T.2N.,R.13E. Set 3/4" Iron Rod with Aluminum Disk Stamped "Macomb County Monument, MI Act 345, #38121" in Monument Box located 600'+/- East of the Intersection of Romeo Plank and East Bound M-59

- Az. 10° 124.33'; Set P.K. Nail w/Tag #38121 in West Face of Traffic Signal Pole.
- Az. 115° 173.57'; Set P.K. Nail w/Tag #38121 in NE Face of Utility Pole
- Az. 174° 53.34'; Found P.K. Nail w/"Macomb County Witness" Tag in E. Face of Utility Pole
- Az. 262° 298.61'; Set P.K. Nail in Top of Curb at East Side of Entry to FNB Bank
- Az. 262° 509.32'; Set P.K. Nail in Conc. Pavement Joint located in Parking Lot for FNB Bank
- Az. 318° 411.46'; Set P.K. Nail in Top of Curb to Westerly Approach to Burger King
- Az. 328° 100.38'; Set P.K. Nail w/Tag #38121 in SW Face of Utility Pole

The Selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by George M. Platz Date 12-13-94
 Surveyor's Michigan License No. 38121

