

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
(County)

Located In: Harrison Township
Corner Code ## A-1

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Register of Deeds Stamp & File Number
Clerk - Register of Deeds
MACOMB COUNTY, MICHIGAN

- 1. Public Land Survey T 2N R 14E A-1
2. Property Controlling in Section S T R
3. Miscellaneous S T R
4. Lot No.
5. Private Claims

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MACOMB COUNTY ROAD COMMISSION (1934) CHESTERFIELD TOWNSHIP / CONTROLLING IN SECTION 31, T. 2N., R. 14E. UNRECORDED CORNER CODE #A-13
L. 3264 P. 502 HARRISON TOWNSHIP / CONTROLLING IN SECTION 6, T. 2N., R. 14E. SODERBERG #17635 CORNER CODE #A-1
L. 4686 P. 039 CHESTERFIELD TOWNSHIP / CONTROLLING IN SECTION 31, T. 3N., R. 14E. GORMAN #17622 CORNER CODE #A-13
L. 3263 P. 895 CLINTON TOWNSHIP / CONTROLLING IN SECTION 1, T. 2N., R. 13E. SODERBERG #17635 CORNER CODE #A-1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE

THIS CORNER VERIFIED BY:

M.D.O.T. RIGHT-OF-WAY DRAWING
MATCHES EDEL FORD - ROSSO SUBDIVISION

SHEET 138
LIBER 38 PAGE 13

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
FRANK J. Dedecker, FS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1" PIPE WITH 3/4" BAR MACOMB COUNTY REMONUMENTATION MARKER #30092
WITNESSES:
N 05. E 40.96' FOUND POINT "<" ANGLE IRON FENCE POST IN CONCRETE
N 40. W 19.59' FOUND PK NAIL IN THE NORTHEAST FACE OF A 4" BASSWOOD TREE
EAST 7.50' FOUND 3/4" PIPE
SOUTH 60.34' FOUND PK NAIL IN THE NORTH EDGE OF ROSSO HIGHWAY
EAST 125.86' FOUND CENTERLINE OF SNOVER ROAD PAVEMENT

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Shelby W. Money
Surveyor's Michigan License No. 30092

Date 12-15-93