

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

C152201

corners in
MACOMB COMMISSION
(County)

Located In: **Shelby Township** Corner Code **#**

LIBER **6527** PAGE **778**

Public Land Survey	T	<u>3N</u>	R	<u>12E</u>	<u>A-13</u>
	T		R		
	T		R		
	T		R		
Property Controlling in Section	S		T		
Miscellaneous	S		T		
Property in Sec.	S		T		

94 DEC 14 AM 10:50

RECORDED
MICHIGAN DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Randy Kolehouse, in a field survey on **June 23**, 19 **94**

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

#	Date	G.L.O.	Notes	Wampler	NA	Post
13	1817	G.L.O.	Notes	Wampler	NA	Post
	1928	MCRC	File #169	NA	NA	Ford Axle in M.B.
	1972	Survey	L. 2271 P. 2	Patterson	#17631	NA
	1974	Survey	L. 2466 P. 726	Kobs	#14097	Iron in M.B.
	1974	L.C.R.C.	L. 2466 P. 738	Kobs	#14097	1/2" Iron in M.B.
	1986	L.C.R.C.	L. 4089 P. 888	Avey	#30076	Boat Spike in M.B.
	1989	L.C.R.C.	L. 04665 P. 607	Patterson	#17631	Boat Spike in M.B.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

13 Found 5/8" rebar with brass cap marked (Oakland Co. Remon. #17632) in Monument Box at center line in intersection of Dequindre and South Blvd.

L.C.R.C. L. 2466 P. 738
PK in D.E. Pole SW 84.2'

L.C.R.C. L. 4089 P. 888
PK/W in Util. Pole SW 84.2'
Nail in Util. Pole SE 88.4'
Nail in Util. Pole NE 86.63'
Nail in Util. Pole NW 85.99'

L.C.R.C. L. 04665 P. 607
Nail in Util. Pole NE 86.63'
Nail in Util. Pole SE 88.40
Nail in Util. Pole SW 84.20'

Measure E 2644.56 to B-13 (G.L.O. 2645.28)
This corner is common with A-1 T2N R12E

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-30-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13 5/8" rebar with Brass Cap stamped "Oakland Co. Remon #17632 in an existing Monument Box.

- PK & Oakland Co. Remon. Tag in NE Face Util. Pole N 38° W 85.96'
- PK & Oakland Co. Remon. Tag in NE Face Util. Pole S 40° E 88.39'
- PK & Oakland Co. Remon. Tag in SE Face Util. Pole N 36° E 86.63'
- PK & Oakland Co. Remon. Tag in Nly Face Util. Pole S 50° W 83.70'



The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Recorded by *Randy J. Kolehouse* Date 10/14/94
Surveyor's Michigan License No. 25854