

**SURVEY &
REMONUMENTATION**

C126161

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

94 SEP 30 AM 9:01

For corners in **COMMISSION**

**CARMEL J. BAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI**

<u>Macomb</u> (County)	Located In: <u>Shelby</u> Township	Corner Code <u>##</u>
1. Public Land Survey	T <u>3N</u> R <u>12E</u>	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

11587 06464PC474

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on August 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - No post set - No bearing trees

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" on a line between the Southeast corner of Section 32 and the South 1/4 corner of Section 32, T4N, R12E, 2460.21 feet West of the Southeast corner of Section 32, which is located 215.94 feet West of the Northeast corner of Section 5, T3N, R12E. The corner is located 71 feet North of the North edge of the West bound lane of 26 Mile Road.

FIELD MEASUREMENT BETWEEN

- D-1 to E-13 (Washington Twp.) 2460.21 Feet
- D-1 to D-13 (Washington Twp.) 215.94 Feet
- D-1 to C-1 2716.42 Feet
- D-1 to E-1 2716.42 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-30-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-1 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623".
- Due West 54.01' Set PK & Remon. Washer North face Power Pole
- N17°E 29.46' Set PK & Remon. Washer North face 14" Oak
- N76°E 73.41' Set PK & Remon. Washer SE face 23" Oak
- S63°E 36.72' Set PK & Remon. Washer SW face 16" Oak

The selected location is a careful and faithful re-establishment of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date SEP 30 1994

