

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C152189

COMMISSION

corners in

Macomb
(County)

Located In: Shelby
Twp.

Corner Code ##

Public Land Survey		T <u>3N</u>	R <u>12E</u>		E-1
		T _____	R _____		_____
		T _____	R _____		_____
		T _____	R _____		_____
Property Controlling in Section	S _____	T _____	R _____		_____
	S _____	T _____	R _____		_____
Miscellaneous Property in Sec.	S _____	T _____	R _____		_____
	S _____	T _____	R _____		_____

LIBER **6527** PAGE **766**

94 DEC 14 AM 10:49

CARRIE BAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. _____ Recorded Plat _____
Private Claims _____

Huston K. Kennedy, in a field survey on September 10, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as pressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post on the Township line 2.67 chains East of found post; 14" White Oak S48*W 24 Links; 14" White Oak S68*E 19 Links;
- 1.) 1988-Avey, P.S. #30076; LCRC L.4353, Pg.432 - Fnd 1" Bar
- 2.) 1990-Patterson, P.S. #17631; LCRC L.4899, Pg.725 - Fnd 1" Iron

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Pipe 78' North of the centerline of the West bound lane of 26 Mile Road, and a tree-fence row extending to the North on the East line of Cannon Cemetery. The Southeast corner of Section 32 and the Southwest corner of Section 33, T4N, R12E, is located 256.12 feet to the West.

Witnesses from LCRC #2 were used to recover and verify the location of the found 1" Iron Pipe.

FIELD MEASUREMENT BETWEEN

- E-1 to F-1 2642.81 Feet
- E-1 to D-1 2716.42 Feet
- E-1 to E-2 2874.30 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 9-20-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-1 I replaced the found 1" Iron Pipe with a 3/4" x 24" Iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623".
- N06°W 54.06' Set PK & Remon. Washer West face 23" Maple
- N67°W 36.69' Set PK & Remon. Washer South face Power Pole
- N82°E 141.43' Set PK & Remon. Washer South face Power Pole
- S84°W 50.74' Set PK & Remon. Washer SE face 9" Ash

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Accepted by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date September 20, 1994