

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C104998

For corners in

<u>Macomb</u> <small>(County)</small>	Located In: <u>Shelby</u> Township	Corner Code <u>#</u>
1. Public Land Survey	T <u>3</u> N R <u>12</u> E	<u>E-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LIBER **06415PC475**
94 AUG -5 PM 1:42
CARMELLA SABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on July 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 14" White Oak S48*W 24 Links; 14" White Oak S68*E 19 Links
- 1976-Avey, P.S. #15396; LCRC L.2666, Pg.852 - Fnd 1/2" Pipe in a Monument Box
 - 1979-Kobs, P.S. #14097; LCRC L.3126, Pg.162 - Fnd 1/2" Pipe in a Monument Box
 - 1988-Avey, P.S. #30076; LCRC L.4353, Pg.434 - Fnd 1/2" Pipe in a Monument Box
 - 1993-Avey, P.S. #30076; LCRC L.5947, Pg.064 - Fnd 1/2" Pipe in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Pipe in a Monument Box 4' West of the centerline of Mound Road, which has a bituminous surface, and a tree row extending to the East & West on the South side of a gas easement.

The witnesses from LCRC #1, 2, 3 & 4 were used to recover and verify the location of the found 1/2" Iron Pipe in a Monument Box.

FIELD MEASUREMENT BETWEEN

E-2 to E-1 2874.30 Feet
E-2 to E-3 2640.53 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-19-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-2 I replaced the found 1/2" Iron Pipe in a Monument Box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
- S84°E 44.25' Set PK & Remon. Washer South face 14" Poplar
 - S21°W 98.14' Set PK & Remon. Washer East face Power Pole
 - S78°W 29.97' Set PK & Remon. Washer North face 10" Elm
 - N29°W 124.91' Set PK & Remon. Washer NE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the available evidence to the position of the original corner.



Signed by Huston K. Kennedy Date July 21, 1994
Surveyor's Michigan License No. 17623