

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code #
<u>Macomb</u>	<u>Shelby Twp.</u>	
(County)		
1. Public Land Survey	T <u>3N.</u> R <u>12E.</u>	<u>E-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Jeffrey A. Wright, in a field survey on May 9, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:


Date	Surveyor	Number	Type	L.	P.	Monument Box
1817	Wampler		Set Post	GLO Records		No

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No monumentation found; extended S. line Lake Valley Sub. to intersect w/ line represented in Job #74614-1196

Location supported by corners in:
 Lake Valley Sub. L. 72, P. 41-42
 S/P of Eyster's Shelby Farms L. 20, P. 43

Fits call in:
 ULC Job #74614-1196


Ground GLO Grid
 E-10-E-9 = 2477.17' 2640/740 Chains 2476.88'
 E-10-E-11 = 2971.85' 2640/740 Chains 2971.51'
 ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-23-97

 WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a Concrete Monument with an aluminum cap stamped "Macomb County Monument - MI Act 345 of 1990" in remains of a N-S. wire fence

- AZ 80° 23.66' to Mag nail with remonumentation tag N'ly side 10" Poplar
- AZ 115° 27.55' to Mag nail with remonumentation tag S'ly side 12" Tree
- AZ 178° 29.89' to Mag nail with remonumentation tag E'ly side 36" Oak
- AZ 273° 17.55' to Mag nail with remonumentation tag S. side 10" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by 

Date: 2 DECEMBER 1997

Surveyor's Michigan License No. 40165

