

**SURVEY & REMONUMENTATION**

C152190

APR 28 1995

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

or corners in

Macomb (County) Located In: Shelby Twp. Corner Code # F-1

Public Land Survey T 3N R 12E

Property Controlling in Section S T R

Miscellaneous S T R

Property in Sec. S T R

LIBER 6527 PAGE 767

94 DEC 14 AM 10:50  
 REG. DEEDS  
 MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Huston K. Kennedy in a field survey on September 10, 1994 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as crossed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

Glo Notes - No post set No bearing trees  
 1.) "Outline Survey" by MCS and Associates, Inc.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - After reviewing copies of the map of Shelby Township dated 1875 & 1916, there is not a land division on the North-South 1/4 line of Section 4, North of the Center Post and there is no line of occupation extending to the South from 26 Mile Road. I found a 1/2" Iron Rod w/cap #10065 RLS at the theoretical location based upon the accepted location of the Northwest and Northeast corners of Section 4. The South 1/4 corner of Section 33, T4N, R12E, is 127.93 feet to the West. The North 1/4 corner is 13' South of the South edge of the East bound lane of 26 Mile Road, which has concrete surface.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94  
 William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

FIELD MEASUREMENTS BETWEEN

F-1 to G-1 2642.81 Feet  
 F-1 to E-1 2642.81 Feet

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 I replaced the 1/2" Iron Rod w/cap #10065 RLS with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623".  
 S44°E 48.20' Set PK & Remon. Washer NE face clump of Willows  
 S10°W 26.72' Set PK & Remon. Washer East face 9" Willow  
 S71°W 58.00' Set PK & Remon. Washer SE face 11" Poplar  
 N76°W 60.72' to the "+" in Sta. 126+00



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

by Huston Kennedy Date September 20, 1994  
 Surveyor's Michigan License No. 17623