B997880

## LAND CORNER RECORDATION CERTIFICATE

93 DEC 22 AM 9: 03

6

10

11

12

For corners in		Filing Requirement of Act 74, Mich. P.A. 19.			
	MACOMB	Located In:	Corner Code ##	CÀRMELLA SABAUGH REGISTER OF DEEDS MACOMB COUNTY, MI	
	(County)	SHELBY TWP.		MACOMB COUNTY, MI	
1.	Public Land Survey	т <u>3N</u> R <u>12E</u>	F-13		
		T R		004 04 M080	
		T R T R		uner 06161 M 230	
2.	Property Controlling	S R			
	in Section	S T R			
3.	Miscellaneous	S T R		Register of Deeds Stamp & File Number	
	Property in Sec.	S R			
4.	Lot No	, Recorded Plat	·-	ABCDEFGHIJKL	
5.	Private Claims			2	

**NOVEMBER 18** 93 **BRUCE ANTCLIFF** , in a field survey on . . 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration: GLO-Post, (AS F13,T3N,R12E) NO WITS. REMAIN

MDOT (F1,T2N,R12E)-REROD IN 1/2" IP (1970) SERVICE POLE, N11W, 59.19' H.T.TOWER. S30E, 52.82 33" MAPLE, N64W, 64.97

P.P., S22W, 35.78' LCRC (1988) L4507,P846 (F13,3N,12E)-1/2" IP MON BOX CHISELED "+" NW LEG TOWER, SOUTH, 73.29" MDOT N&T IN PP, N05W, 58.10"


MDOT (F13,T3N,R12E)-1/2" IP IN MON BOX (1988) CHISELED "+" NW LEG TOWER, SOUTH, 73.29" MDOT N&T IN PP, NO5W, 58.10" MDOT N&T IN 23" MAPLE, N40W, 51.53" MDOT N&T IN PP. \$40E, 44,701

ALL RECORDS INDICATE THAT THIS CORNER IS COMMON TO BOTH T2N, R12E & T3N, R12E.

MDOT N&T IN 23" MAPLE, N40W, 51.53" MDOT N&T IN PP, S40E, 44.70° Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE IN MON BOX FOUND AND VERIFIED THREE OF THE ABOVE WITNESSES.

MDOT (1970) MEASURED 2656.19' TO NW SEC. 4; WE MEASURED 2655.96'



ATE OF MICHIGA

BRUCE

ANTCLIFF

SURVEYOR

×

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET MACOMB COUNTY REMONUMENTATION MARKER AND CAP #25826 IN EXIST. MON. BOX. WITNESSES

FOUND MOOT N&T N SIDE PP, S47E, 44.71' FOUND MOOT N&T W SIDE PP, N11W, 58.09' FOUND MDOT N&T W SIDE 24" MAPLE (DEAD), N44W, 51.48" SET NAIL & MCM TAG N SIDE PP, S73W, 107.00' TOP CENTER FIRE HYDRANT, N46W, 38.78'

SET NAIL & MCM TAG N SIDE PP, S73W, 107.00' TOP CENTER FIRE HYDRANT, N46W, 38.78'		SURVEYOR No. 25826
The selected location is accepted by me and is generally accepted the best available evidence of the position of the original corner.	by Professional Surveyors as	NAME OF THE PARTY
Signed by Bruce Outsliff	Date	
Surveyor's Michigan License No. 25826	FORM APPROVED BY MICHIGA	N STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975