

FEB 27 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb  
(County)

Located In:  
Shelby Twp.

Corner Code #

1. Public Land Survey	T	<u>3N.</u>	R	<u>12E.</u>	<u>G-4</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Jeffrey A. Wright, in a field survey on June 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-27-96  
William E. Soderberg  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9	•	10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Date	Surveyor	Number	Type	L.	P.	Monument Box
1817	Wampler		Set Post	GLO Records		No
1978	Dewinter	25839	F. PK & Washer	3031	884	No
1993	Avey	30076	F. PK	Unrecorded		No
1994	King	30085	F. PK	6586	221	No
Unknown	MCRC		Unknown	Unrecorded		Unknown
<i>This document does not fit the following witnessed corner</i>						
1979	Coulter	14760	F. 3/4" Pipe	3116	516	No

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

S. Mag nail from previous accepted witnesses

Fits call in:	Location supported by corners in:	GLO
L. 3031, P. 884 F. PK & Washer	S/P of Ross S L. 31, P. 40	G-4 - G-3 = 2630.49' 2640' / 40 chains
L. 6586, P. 221 F. PK	S/P of Disco L. 17, P. 12	G-4 - G-5 = 2641.84' 2640' / 40 chains
	Bel-air Sub. L. 32, P. 19	

*C0438546 LIBER:07245 PAGE:407 08:59A 11/14/1996*  
*CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

Replaced Mag nail w/ 3/4" Bar in new monument box w/ aluminum cap stamped "Macomb County Monument - MI Act 345 of 1990"

- AZ 269° 51.16' to Mag nail with remonumentation tag S. side U. Pole
- AZ 341° 156.79' to Mag nail with remonumentation tag NE side U. Pole
- AZ 9° 243.17' to centerline top hydrant
- AZ 17° 127.76' to Mag nail with remonumentation tag NW side U. Pole
- AZ 102° 97.27' to Mag nail with remonumentation tag N side 12" Pine



The selected location is accepted by me and is generally accepted by Professional Surveyor's as the best available evidence of the position by the original corner.

Signed by Jeffrey A. Wright Date: 16 OCTOBER 1996  
Surveyor's Michigan License No. 40165