

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Macomb</u> (County)	Located In: <u>Shelby</u> <u>Twp.</u>	Corner Code # <u>G-11</u>
1. Public Land Survey	T <u>3N.</u> R <u>12E.</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SURVEY &
 RE-MONUMENTATION**

APR 20 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Warren C. Avey, in a field survey on September 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Date	What	L.	P.	Who	Surveyor's ID	Corner Type	Mon. Box
1817	GLO			Wampler	N/A	Post	No
1974	LCRC	2555	347	Pawlaczyk	17632	?	?

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1 1/2" Bar in Monument Box in Asphalt over Conc. Pavement

Fits L. 2555 P. 347 62.14' S.E. GW Tag in N.E. face U. Pole
 69.43' N.W. GW Tag in N.E. face U. Pole

Location supported by corners in: S/P Wallace Sub. L.18, P.41 G-11 - G-10 = 2649.23'
 S/P Burton-VanDyke Gardens L.16, P.12 G-11 - H-11 = 2654.40'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted 1 1/2" Bar in existing Monument Box

AZ 130° 62.04' to set PK nail in MCW tag in N.E. face U. Pole
 AZ 239° 69.43' to PK nail in S.E. face U. Pole
 AZ 315° 69.33' to nail in MCRC Disc N.W. face U. Pole
 AZ 59° 83.81' to PK nail in Disc in N.W. face U. Pole

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-27-94

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

The selected location is accepted by me and is generally accepted by Professional Surveyor's as the best available evidence of the position of the original corner.

Signed by *Warren C. Avey*
 Surveyor's Michigan License No. 30076

