

LIBER 06166 037

B999650

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County) Located in: Shelby Twp. Corner Code # I-5

1. Public Land Survey T 3 N R 12 E

2. Property Controlling in Section S T R

3. Miscellaneous Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.
DEC 28 1993
L. J. Decker
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN
Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 11" Ash S54°W 28 Lnks; 9" Ash N85°E 23 Lnks
- 1972-Avey, P.S. #15396; LCRC L.2268, Pg.54 - Fnd 5/8" Iron Rod in a monument box
- 1974-Kobs, P.S. #14097; LCRC L.2534, Pg.471 - Fnd 1/2" Iron Rod
- 1979-Fenn, P.S. #23505; LCRC L.3168, Pg.264 - Fnd 3/8" Iron Rod
- 1986-Avey, P.S. #30076; LCRC L.3945, Pg.714 - Fnd 1/2" Iron Rod #17635 in monument box
- 1990-Avey, P.S. #30076; LCRC L.4983, Pg.766 - Fnd 1/2" Iron Rod #17635 in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a monument box located in the centerline of Jewell Road to the North, and 1.5' North of the centerline of 24 Mile Road. Both are bituminous surface roads.

All witnesses from the fifth LCRC above were found and they were used to recover and verify the location of the found 1/2" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93.
FRANK J. DÖDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-5 I replaced the found 1/2" Iron Rod in a monument box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
- N40°E-46.31'-Set PK & Remon. tag in SW face Power Pole
- N74°W-127.51'-Set PK & Remon. tag in SW face 27" Elm
- S72°W-94.41'-Set PK & Remon. tag SE face Power Pole
- S05°E-26.03'-Set PK & Remon. tag West face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy Date 12/14/93
Surveyor's Michigan License No. 17623

