

LIBER 061680067

13999680

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Shelby Twp.

Corner Code #/

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk of Deeds, Macomb County, Michigan

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 12 E I-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column H and row 7.

I, Huston K. Kennedy, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post; 5" Ash N77 1/2 W 9 Lnks; 11" Red Oak S44 E 15 Lnks
1973-Smith, P.S. #16052; LCRC L.2414, Pg.502 - Fnd 3/4" Iron Pipe in a monument box
1979-Fenn, P.S. #23505; LCRC L.3168, Pg.269 - Fnd 1" Iron
1991-Avey, P.S. #30076; LCRC L.5063, Pg.826 - Fnd nail in disk
1992-Donnelly, P.S. #21563; LCRC L.5298, Pg.945 - Same wits as 1979 LCRC
1992-Avey, P.S. #15396; Survey L.5700, Pg.475 - Same wits as 1991 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd Nail & Washer located in the centerline of 23 Mile Road, which is concrete surface.

Two witness points from the 1991 LCRC above were found and they were used to recover and verify the found Nail & Washer.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93.
Signature of Frank J. DeDecker, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-7 I replaced the found Nail & Washer with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
S69 E-46.25'-Set Nail & Washer South edge conc.
S01 E-17.21'-Fnd Nail & Washer South edge conc.
N55 E-54.43'-Set Nail & Washer North edge conc.
N03 E-31.08'-Set Nail & Washer North edge conc.

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]

Date 12/10/93

Surveyor's Michigan License No. 17623