

**SURVEY &
REMONUMENTATION**

FEB 27 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Macomb</u> (County)	Located In: Shelby Twp.	Corner Code #
1. Public Land Survey	T <u>3N.</u> R <u>12E.</u>	<u>I-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Wright, in a field survey on June 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-23-96

William E. Squibberg
WILLIAM E. SQUIBBERG, P.S., CHAIRMAN

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Date	Surveyor	Number	Type	L.	P.	Monument Box
1817	Wampler		Set Post			GLO Records No
1939	Unknown		F. Ford Axle			Unrecorded No
1972	Avey	15396	F. 3/4" bar			Unrecorded Yes
1973	Avey	15396	F. 3/4" bar			Unrecorded Yes
1978	Avey	15396	F. 3/4" bar			Unrecorded Yes
1982	Avey	15396	F. 3/4" bar			Unrecorded Yes
1984	Avey	15396	F. 3/4" bar			Unrecorded Yes
1987	Erickson	16929	F. 3/4" Iron	4328	564	Yes
1991	Avey	30076	F. 3/4" Iron	5063	825	Yes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F. 3/4" Bar in existing monument box 1 (+/-) S. of centerline of asphalt road

Fits call in:

L. 4328, P. 564
L. 5063, P. 825

F. 3/4" Iron
F. 3/4" Iron

Location supported by corners in:

Forest Lake Sub.
Shelby Woods Sub.
Shelby Woods Sub. #2

L. 89, P. 18-23
L. 78, P. 16-17
L. 78, P. 18-19

I-9 - I-8 = 2623.59'
I-9 - I-10 = 2631.34'
I-9 - H-9 = 2661.98'
- J-9 = 2625.85'

GLO

2640' / 40 chains
2640' / 40 chains
2640' / 40 chains
2640' / 40 chains

**C0438549 LIBER:07245 PAGE:410 08:59A 11/14/1996
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed aluminum cap stamped "Macomb County Monument - MI Act 345 #40165" on 3/4" bar in existing monument box

- AZ 237° 16.74' to Mag nail with remonumentation tag top of guard rail post
- AZ 174° 19.88' to Mag nail with remonumentation tag top of guard rail post
- AZ 338° 28.70' to Mag nail with remonumentation tag top of guard rail post
- AZ 50° 32.41' to Mag nail with remonumentation tag top of guard rail post
- AZ 260° 48.02' to nail in SE corner concrete bridge rail
- AZ 300° 51.66' to nail in NE corner concrete bridge rail

The selected location is accepted by me and is generally accepted by Professional Surveyor's as the best available evidence of the position by the original corner.

Signed by *Jeffrey A. Wright*

Date: 16 OCTOBER 1996

Surveyor's Michigan License No. 40165

