

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

C126169

94 SEP 30 AM 9: 01

CARMILO A. SABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

For corners in

<u>Macomb</u> (County)	Located In: <u>Shelby Township</u>	Corner Code <u>##</u>
1. Public Land Survey	T <u>3N</u> R <u>12E</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

116FR 06464PC482

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Huston K. Kennedy, in a field survey on August 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Glo - No post set - No bearing trees

- 1.) 1980-Kobs, P.S. #14097; Survey L.3287, Pg.549 - Fnd 1" Pipe in a Monument Box
- 2.) 1990-Kobs, P.S. #14097; Survey L.5014, Pg.676 - Fnd 1" Pipe in a Monument Box, used same wit as 1980 LCRC
- 3.) 1968-Macomb County Road Comm. Fnd - 1.5" Iron Pipe
- 4.) 1967-Macomb County Road Comm. Fnd - 1" Pipe
- 5.) 1993-Kennedy, P.S. #17623; LCRC L.6166, Pg.028 - Set 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a Monument Box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" x 24" Iron Rod w/2" diameter cap stamped "Macomb County Monument MI Act 345 #17623" in a Monument Box 1.5' North of the centerline of 26 Mile Road, which has a bituminous surface. The North 1/4 corner of Section 2, T3N, R12E, is being used and accepted as common corners with South 1/4 corner of Section 35, T4N, R12E.

FIELD MEASUREMENTS BETWEEN

- J-1 to K-1 2641.39 Feet
- J-1 to I-13 (Washington Twp.) 2640.74 Feet
- J-1 to I-1 2686.54 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-16-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 I found 3/4" x 24" Iron Rod w/2" diameter cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
N06°E 123.24' Fnd PK Nail & Remon. Washer in West face 34" Elm
S62°E 68.05' Fnd PK Nail & Remon. Washer in NE face Power
S45°W 43.05' Fnd PK Nail & Remon. Washer in NW face 30" Box Elder
S70°W 90.59' Fnd PK Nail & Remon. Washer in NW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston Kennedy*
Surveyor's Michigan License No. 17623

Date August 1, 1994