

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Shelby Twp.

Corner Code #/

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Leonard J. Decker, Clerk - Recorder of Deeds, Macomb County, Michigan

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 12 E J-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 7, column J.

I, Huston K. Kennedy, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.: Set Post; 9" Beech N67°W 17 Lnks; 7" Beech S18°E 21 Lnks
1979-Fenn, P.S. #23505; LCRC L.3168, Pg.268 - End 1" Pipe
1984-Avey, P.S. #15396, LCRC L.3644, Pg.455 - End PK Nail
1985-Avey, P.S. #15396, LCRC L.3817, Pg.911 - Same wits as 1984 LCRC
1992-Donnelly, P.S. #21563; LCRC L.5298, Pg.945 - Same wits as 1984 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - End 3/4" Iron Rod in a monument box located 2.75' South of the centerline of 23 Mile Road, which is bituminous surface.

The witnesses from the 1984 LCRC above were found and they were used to recover and verify the found 3/4" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-7 I replaced the found 3/4" Iron Rod in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
N77°W-157.10'-Set PK & Remon. tag SW face Power Pole
N49°W-91.00'-Set PK & Remon. tag above existing witness SW face 24" Pine
N01°W-35.29'-Set PK & Remon. tag West face Power Pole
S01°E-85.94'-Set PK & Remon. tag above existing witness West face 15" Apple

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12/14/93

