

**SURVEY &  
REMONUMENTATION**

APR 28 1995

C126170

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

94 SEP 30 AM 9:01

**COMMISSION**

For corners in

<u>Macomb</u> (County)	Located In: <u>Shelby</u> Township	Corner Code <u>##</u>
1. Public Land Survey	T <u>3</u> N R <u>12</u> E	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

CARL W. BAUGH  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

LIBER 06464PC483

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on July 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post at Northwest corner of Section 1 and Northeast corner of Section 2 on the Township line 0.69 chains East of corner common to Section 35 & 36, T4N, R12E, 13" Poplar N84\*W 9 Links; 8" Beech S39\*E 11 Links;
- 1972-Kobs, P.S. #14097; LCRC L.2268, Pg.677 - Fnd 5/8" Iron Bar in a Monument Box.
  - 1972-Kobs, P.S. #14097; Survey L.2268, Pg.671 - Fnd 5/8" Iron Bar in a Monument Box, used same wit as 1972 LCRC
  - 1972-Kobs, P.S. #14097; Survey L.2370, Pg.382 - Fnd 5/8" Iron Bar in a Monument Box, used same wit as 1972 LCRC
  - 1977-Kobs, P.S. #14097; Survey L.2882, Pg.467 - Fnd 5/8" Iron Bar in a Monument Box, used same wit as 1972 LCRC
  - 1977-Kobs, P.S. #14097; Survey L.2882, Pg.440 - Fnd 5/8" Iron Bar in a Monument Box, used same wit as 1972 LCRC
  - 1988-Kobs, P.S. #14097; Survey L.4543, Pg.96 - Fnd 5/8" Iron Bar in a Monument Box, used same wit as 1972 LCRC
  - 1993-Kennedy, P.S. #17623; LCRC L.6166, Pg.029 - Set 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a Monument Box 1.25' South of the centerline of 26 Mile Road, which has a bituminous surface, and in the center of Schoenherr Road to the North, and 3' West of the center of Schoenherr Road to the South, which has a gravel surface North & South. The Northwest corner of Section 1 and the Northeast corner of Section 2, T3N, R12E, are being used and accepted as common corner with the Southeast corner of Section corner of Section 35, and the Southwest corner of Section 36, T4N, R12E.

Witnesses from LCRC #1 & 7 were used to recover and verify the location of the found 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a Monument Box.

FIELD MEASUREMENT BETWEEN

K-1 to L-1 2660.38 Feet  
K-1 to J-1 2641.39 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-16-94

*William E. Soderberg*  
WILLIAM E. SODERBERG P.S. CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 I found a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act #17623" in a existing Monument Box.  
N23°E 125.31' Fnd PK & Remon. Washer in West face 28" Pine  
N11°W 152.05' Fnd PK & Remon. Washer in East face 20" Ash in clump of 5  
S60°W 55.96' Fnd PK & Remon. Washer above existing witness in NW face Power Pole  
S45°E 44.15' Fnd PK & Remon. Washer in SW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date August

