

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Shelby Twp.

Corner Code #

RECORDED IN MACOMB COUNTY
RECORDED AT: 8:30 A.M.

DEC 23 1993

James H. ...
CLERK OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 12 E K-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid with columns A-L and rows 2-13. A dot is present at row 3, column K.

I, Huston K. Kennedy, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set Post; 6" White Oak N45°W 50 Lnks; 40" White Oak N57°E 37 Lnks 1972-Kobs, P.S. #14097; Survey L.2268, Pg.672 - Fnd 3/4" Iron Rod in a monument box 1972-Kobs, P.S. #14097; LCRC L.2268, Pg.675 - Fnd 3/4" Iron Rod in a monument box 1976-Avey, P.S. #15396; Survey L.2717, Pg.305 - Fnd 3/4" Iron Rod in a monument box 1978-Avey, P.S. #15396; Survey L.3001, Pg.173 - Same wits as 1976 survey 1979-Kobs, P.S. #14097; Survey L.3186, Pg.867 - Same wits as 1972 survey 1983-Kobs, P.S. #14097; Survey L.3465, Pg.196 - Same wits as 1972 survey 1987-King, P.S. #30085; Survey L.4151, Pg.89 - Same wits as 1972 survey 1990-Avey, P.S. #30076; LCRC L.5014, Pg.014 - Fnd rusted bar in monument box 1991-King, P.S. #30085; Survey L.5101, Pg.621 - Fnd 3/4" Iron Rod in monument box

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod in a monument box in the centerline of Schoenherr Road, which is gravel surface to the North and bituminous surface to the South, and 3.5' South of the centerline of 25 Mile Road, which is bituminous surface.

Three witness points from the 1990 LCRC were found and they were used to recover and verify the location of the found 3/4" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93 FRANK J. DeDECKER, PS, PE, CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: K-3 I replaced the found 5/8" Iron Rod in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box. N27°E-69.60'-Set PK & Remon. tag NW face 30" Walnut N23°W-91.17'-Set PK & Remon. tag NW face 19" Walnut S55°W-56.91'-Set PK & Remon. tag SE face Power Pole S82°E-138.35'-Set PK & Remon. tag North face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available residence of the position of the original corner.

Signed by *Huston K. Kennedy* Surveyor's Michigan License No. 17623

Date *12/14/93*

