

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb

(County)

Located In: Shelby Twp.

Corner Code #

RECORDED IN MACOMB COUNTY
RECORDED 8:30 A.M.

DEC 28 1993

Lermilla Joseph
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 12 E K-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Huston K. Kennedy, in a field survey on December 14, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1817-GLO Wampler, D.S.; Set Post; 8" White Oak N61 1/2°W 16 Lnks; 6" Maple N68 1/2°E 23 Lnks
 - 1976-Avey, P.S. #15396; Survey L.2717, Pg.305 - Fnd 5/8" Iron Rod in a monument box
 - 1976-Avey, P.S. #15396; LCRC L.2718, Pg.736 - Same wits as 1976 survey
 - 1978-Avey, P.S. #15396; Survey L.3001, Pg.173 - Same wits as 1976 survey
 - 1978-Kobs, P.S. #14097; Survey L.3021, Pg.189 - Fnd 5/8" Iron Rod in a monument box
 - 1978-Kobs, P.S. #14097; LCRC L.3021, Pg.205 - Same wits as 1978 survey
 - 1987-King, P.S. #30085; LCRC L.4151, Pg.126 - Fnd 1/2" Iron Rod
 - 1990-Avey, P.S. #30076; LCRC L.4983, Pg.762 - Fnd 1/2" Iron Rod in monument box
 - 1992-Avey, P.S. #30076; Survey L.5290, Pg.298-299 - Same wits as 1990 LCRC

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a monument box located in the centerline of Schoenherr Road, which bituminous surface. There are tree lines extending to the East and West.

One witness point from the 1990 LCRC was found and it was used to recover and verify the location of the found 1/2" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93.

Frank J. DeDecker
FRANK J. DeDECKER, PS, PE, CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- K-4 I replaced the found 1/2" Iron Rod in a monument box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
- N43°E-39.27'-Set PK & Remon. tag NW face 29" Ash
 - N85°E-53.57'-Set PK & Remon. tag North face Power Pole
 - S47°E-101.40'-Set PK & Remon. tag NE face 13" Maple
 - S89°W-52.83'-Set PK & Remon. tag North face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *H.K. Kennedy*
Surveyor's Michigan License No. 17623

Date 12-14-93

