

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

For corners in

Macomb (County)

Located In: Shelby Twp.

Corner Code #

- 1. Public Land Survey T 3 N R 12 E K-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

DEC 28 1993

Signature of Clerk - Register of Deeds, Macomb County, Michigan

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column J and row 5.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 5" Beech N07°E 18 Lnks; 5" Beech S38 1/2°E 6 Lnks
1974-Avey, P.S. #15396; LCRC L.2496, Pg.762 - Fnd 1/2" Pipe
1974-Kobs, P.S. #14097; LCRC L.2499, Pg.414 - Fnd 3/4" Pipe
1980-Kobs, P.S. #14097; LCRC L.3217, Pg.662 - Fnd 3/4" Pipe in a monument box
1987-King, P.S. #30085; Surveys L.4151, Pg.89,94 - Fnd 1/2" Iron w/cap #17635 in monument box
1987-King, P.S. #30085; LCRC L.4151, Pg.126 - Same wits as 1987 surveys
1990-Avey, P.S. #30076; LCRC L.4983, Pg.762 - Fnd 1/2" Iron rod in monument box
1990-Avey, P.S. #30076; Survey L.4983, Pg.735
1992-Avey, P.S. #30076; Survey L.5290, Pg.298-299

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Rod in a monument box located in the centerline of 24 Mile Road, and in the centerline of Schoenherr Road to the South and 3' East of the centerline of Schoenherr Road to the North. Both are bituminous surface roads.

Two witnesses from the 1990 LCRC were found and they were used to recover and verify the location of the found 3/4" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5 I replaced the found 3/4" Iron Rod in a monument box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
S48°E-49.43'-Set PK & Remon. tag in NE face Power Pole
N56°E-43.88'-Set PK & Remon. tag in NW face Power Pole
N48°W-47.25'-Set PK & Remon. tag SW face Power Pole
N80°W-80.15'-Set PK & Remon. tag South face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12/14/93

