

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County) Located In: Shelby Twp. Corner Code # K-6
1. Public Land Survey T 3 N R 12 E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-12. A dot is marked at the intersection of column K and row 6.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set Post; 5" White Oak N77°W 13 Lnks; 8" White Oak S79°E 14 Lnks 1974-Avey, P.S. #15396; LCRC L.2496, Pg.762 - Fnd 1/2" Pipe 1979-Landwehr, P.S. #10065; LCRC L.3102, Pg.146 - Fnd 1/2" Pipe 1980-Kobs, P.S. #14097; LCRC L.3217, Pg.662 - Fnd 1/2" Pipe in a monument box 1988-Avey, P.S. #30076; LCRC L.4353, Pg.435 - Fnd 1/2" Rod in a monument box 1988-Avey, P.S. #30076; Survey L.4353, Pg.448 - Same wits as 1988 LCRC 1991-Avey, P.S. #30076; Survey L.5146, Pg.852-853 - Fnd 3/4" Iron Rod in a monument box

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Rod in the centerline of Schoenherr Road, which is bituminous surface. There are lines of occupation extending to the East and West.

The witness points from the 1991 Certificate of Survey were found and they were used to recover and verify the found 3/4" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93. FRANK J. DODECKER, PS, PE, CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner. K-6 I replaced the found 3/4" Iron rod in monument box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box. S88°W-51.32'-Set PK & Remon. tag in North face Power Pole S23°W-107.53'-Set PK & Remon. tag in SE face Power Pole S77°E-93.90'-NW corner of house #51998 N50°E-132.62'-SW corner of house #13636

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12/14/93

