

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Macomb), Located In (Shelby Twp.), Corner Code (# K-7), and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk - Register of Deeds, Macomb County, Michigan

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a dot in cell G8.

- A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set Post; 5" Beech N88°W 20 Lnks; 14" Beech N54°E 11 Lnks; 1974-Kobs, P.S. #14097; Survey L.2534, Pg.446 - Fnd 1/2" Iron Rod; 1974-Kobs, P.S. #14097; LCRC L.2534, Pg.475 - Same wits as 1974 survey; 1979-Kobs, P.S. #14097; Survey L.3074, Pg.515 - Same wits as 1974 survey; 1979-Landwehr, P.S. #10065; LCRC L.3102, Pg.146 - Same wits as 1974 survey; 1983-Kobs, P.S. #14097; Survey L.3488, Pg.545 - Same wits as 1974 survey; 1984-Kobs, P.S. #14097; Survey L.3579, Pg.129 - Same wits as 1974 survey; 1988-Avey, P.S. #30076; Survey L.4353, Pg.448 - Fnd PK Nail; 1988-Avey, P.S. #30076; LCRC L.4353, Pg.435 - Same wits as 1988 survey; 1990-Avey, P.S. #30076; LCRC L.4983, Pg.765 - Fnd 1" Iron Rod in monument box

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Rod in a monument box located in the intersection of the centerline of 23 Mile Road and Schoenherr Road. Both are bituminous surface roads.

Witness points from the 1988 and 1990 LCRC's were found and they were used to recover and verify the found 1/2" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: K-7 I replaced the found 1/2" Iron Rod in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box. N42°W-56.65'-Set PK & Remon. tag SW face Power Pole; N54°W-60.75'-Set PK & Remon. tag SE face Power Pole; S60°E-70.05'-Set PK & Remon. tag North face Power Pole; S47°W-64.94'-Set PK & Remon. tag NW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12/14/93

