

LIBER 06166007

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

For corners in

Table with columns: Macomb (County), Located In: Shelby Twp., Corner Code #, and numbered items 1-4 describing survey types and their locations.

DEC 28 1993

Signature of Caronella A. ...
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. ... Recorded Plat ...
5. Private Claims ...

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a dot in row 9, column J.

I, Warren C. Avey, in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLC Corner - Set Post - No Witnesses

LCRC 1978 Iron in Mon. Box L. 3023, P. 329
49.33' S 45° E pk nail & MCRC tag N side p. pole
46.18' S 45° W pk nail & MCRC tag N side p. pole
74.81' N 30° W pk nail & MCRC tag SW side p. pole

LCRC 1986 1/2" Bar in Mon. Box L. 4080, P. 886
74.60' NW to pk nail SW face u. pole
46.05' SW to pk nail Ely. face u. pole
52.36' SE to conc. nail in SW face u. pole
2648.72' W to 1/2" bar in mon. box (N 1/4 cor.)

LCRC 1985 1/2" Bar in Mon. Box L. 3829, P. 256
74.60' NW to pk nail in SW face u. pole
46.05' SW to pk nail in ely. face u. pole
52.36' SE to conc. nail in SW face u. pole
2650.72' E to bar in asphalt (1/4 cor)

LCRC 1991 1/2" Bar in Mon. Box L. 5290, P. 288
54.94' SE to pk nail NE side p. pole
54.10' SW to pk nail SE side p. pole
74.62' NW to pk nail in MCRC disc SW side p. pole
48.80' NE to pk nail in concrete curb

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Bar in Mon. Box.

Checked Witnesses

- 54.94' SE to pk nail in the NE side of p. pole
54.10' SW to pk nail in the SE side of p. pole
74.62' NW to pk nail in MCRC tag SW side p. pole
48.80' NE to pk nail in concrete curb

This corner location is supported by existing Survey Pts. in:

- Lancaster Est. Sub. L. 76, P. 4
S/P #2 Shelby Twp. L. 51, P. 19
Proposed Silent Woods Sub #1
Proposed Fox Chase Creek Sub.

Location documented in recorded surveys:

- L. 3062, P. 534
L. 3023, P. 333
L. 3287, P. 569

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced 1/2" B. with 3/4" Bar w/Alum. Cap Stamped "Macomb County Monument - MI Act 345" 30076

- 74.66' NW to pk nail in MCW tag in NE face U. pole
54.05' SW to pk nail in MCW tag in NW face U. pole
54.90' SE to pk nail in MCW tag in NE face U. pole
71.73' NE to chiseled "+" in N rim G & W

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] 30076

Date 12-6-93

Surveyor's Michigan License No. \_\_\_\_\_

