

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

For corners in

Form with fields for County (Macomb), Located In (Shelby Twp.), Corner Code (# K-10), and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

DEC 28 1993

Signature of Camella Anagnost, Clerk - Register of Deeds, Macomb County, Michigan.

Register of Deeds Stamp & File Number

Warren C. Avey, in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13, containing numerical values for survey points.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Corner - Set Post in 1817 - No Witnesses

LCRC 1977 1/2" Bar L. 2775, P. 801
31.70' W to pk nail in p. pole
79.25' SW to pk nail in 36" Willow
31.27' SE to pk nail in 7" Box Elder

LCRC 1986 5/8" Rerod in Mon. Box L. 4058, P. 152
79.36' SW to 60d nail in SE face 40" Willow
32.09' W to 20d conc. nail N. face u. pole
84.56' NW to Top "M" in Mueller on Hyd. 7
140.75' SE to pk nail W face u. pole

LCRC 1986 1/2" Bar in Mon. Box L. 4080, P. 887
85.01' NW to c/l on top nut of f-hyd.
32.05' W to nail in MCRC washer S face u. pole
79.32' SW to pk nail in the SE face 30" Willow
140.70' SE to pk nail in W face guy pole

LCRC 1977 5/8" Bar L. 2806, P. 144
90.26' to 20d conc. nail SW face 3.5' high stump
79.36' W.SW to 20d conc. nail in NW face 24" Willow
32.09' to 20d conc. nail in N. face p. pole
138.00' S.SE to 20d conc. nail W face service pole

LCRC 1991 1/2" Bar in Mon. Box L. 5290, P. 288
32.11' W to pk nail in MCRC disk S. side p. pole
85.00' NW to c/l top f-hyd.
79.45' SW to pk nail S side 36" Willow
140.68' SE to pk nail W side p. pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Bar in Mon. Box.

Checked Witnesses

- 32.11' W to pk nail in MCRC tag S side p. pole
85.00' NW to c/l top f-hyd.
79.45' SW to pk nail S side 36" Willow
140.68' SE to pk nail W side p. pole

This corner location is supported by existing monuments in:
Banbury Meadows Sub. L. 69, P. 10-12
Parklawn Estates Sub. L. 70, P. 15-17
Pheasant Run Sub. L. 89, P. 24
Proposed Silent Woods Sub #1
Proposed Fox Chase Creek Sub.

Location documented in recorded surveys:

- L. 2775, P. 782
L. 3062, P. 528
L. 3084, P. 943

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" B. with 3/4" Bar w/Alum. Cap Stamped "Macomb County Monument - MI Act 345" 30076

- 31.74' W to pk nail in MCW tag N face u. pole
78.13' SW to pk nail in MCW tag in Nly face 40" Willow
85.03' NW to chiseled "+" in top of f-hyd.
126.95' NE to chiseled "+" in W rim san. M.H.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 30076

Date 12-6-93

