

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Macomb (County), Located In: Shelby Twp., Corner Code: K-12, and numbered items 1-5 describing survey details.

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Lesnelle Avey, Clerk - Register of Deeds, Macomb County, Michigan.

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a dot in cell 12-36.

I, Warren C. Avey, in a field survey on November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Corner - Set Post in 1817 - No Witnesses

LCRC 1974 1/2" Iron Rod L. 2500, P. 806
32.63' E to 12" Ash
119.66' S. 25' W. power pole

LCRC 1977 1/2" Iron Bar L. 2898, P. 387
59.19' NE to SW face Buckeye pipeline ID post
32.27' E to pk nail & brass tag in 12" tree
52.84' SW to NE face Buckeye pipeline ID post

LCRC 1976 1/2" Bar in Mon. Box L. 2701, P. 389
59.22' NE to top 3" dia. steel stand pipe
32.65' E to nail & washer 12" tree
119.66' SW to nail & MDSH cap in p. pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Bar in Mon. Box.
Checked Witnesses
53.59' SW to NE face Buckeye pipeline
ID post (post is tilted SW approx. 0.7")
All others destroyed

This corner location is supported by existing survey pts. in:
Schoenherr - 21 Gardens Sub. L. 43, P. 24
Schoenherr - 21 Gardens Sub. #1 L. 52, P. 36

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-10-93.
Signature of Frank J. Decker, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" B. with 3/4" Bar w/Alum. Cap Stamped "Macomb County Monument - MI Act 345" 30076
57.17' SE to pk nail in MCW tag in SW face Guy pole
57.94' SW to pk nail in MCW tag in SE face U. pole
49.18' W.SW to Chiseled "+" in top of f-hyd.
189.98' NW to pk nail in MCW tag in U. pole

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by [Signature] 30076
Surveyor's Michigan License No.

Date 12-6-93