

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

B997884

For corners in

MACOMB

(County)

Located In:

Corner Code #

SHELBY TWP.

- |                                    |                          |                    |
|------------------------------------|--------------------------|--------------------|
| 1. Public Land Survey              | T <u>3N</u> R <u>12E</u> | <u>K-13</u>        |
|                                    | T _____ R _____          | _____              |
|                                    | T _____ R _____          | _____              |
|                                    | T _____ R _____          | <u>Seg. # 1 pm</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____              |
|                                    | S _____ T _____ R _____  | _____              |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____              |
|                                    | S _____ T _____ R _____  | _____              |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

LIBER 06161 PG 234

Register of Deeds Stamp & File Number

I, BRUCE ANTCLIFF, in a field survey on NOVEMBER 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO-Post, NO WITS. REMAIN

MDOT & LCRC(1974) L2500,P802- 1" ROD IN MON BOX  
 PP, S30W, 66.98'  
 PP, N20W, 66.70'  
 TEL. POLE, N30E, 82.50'

LCRC (1986) L4353,P441, -1/2" BAR IN MON BOX  
 NW BOLT SIGN POST BASE, SE, 98.66'  
 SE BOLT SIGN POST BASE, SW, 108.37'  
 MCRC N&T SE FACE GUY POLE, NE, 62.29'  
 CONC NAIL NW FACE U.P., NW, 68.23'

LCRC (1974) L2501,P413-1" IRON IN MON BOX  
 RR SPIKE IN POLE, N26W, 66.00'  
 PK IN PP, N24E, 92.10'  
 PK IN POLE, S26W, 66.70'

LCRC (1989) L4828,P156, -FORM PIN  
 "X" NW BOLT MARATHON SIGN, SE, 90.31'  
 MDOT N&T SE FACE UTIL POLE, NE, 64.80'  
 MDOT N&T SW FACE UTIL POLE, NW, 66.51'  
 N&T #46304 S FACE UTIL POLE, WNW, 72.29'  
 N&T #19005 NW FACE UTIL POLE, SW, 68.51'

MDOT(1990) 1/2" REBAR & CAP IN MON BOX  
 NW BOLT MARATHON SIGN, S45E, 90.39'  
 MDOT N&T IN UTIL POLE, N35E, 64.91'  
 MDOT N&T IN UTIL POLE, N30W, 66.66'  
 MDOT N&T IN UTIL POLE, N45W, 72.29'  
 MDOT N&T IN UTIL POLE, S25W, 68.54'

ACCORDING TO GLO RECORDS AND SUBSEQUENT PLAT AND SURVEY RECORDS, THIS CORNER IS COMMON TO BOTH T2N, R12E & T3N, R12E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 FOUND 1/2" REBAR/MON. BOX

FOUND AND VERIFIED TWO OF THE ABOVE WITNESSES

VERIFIED MDOT DISTANCE SOUTH TO K-2

93 DEC 22 AM 9: 04

CARMELLA SABAUGH  
 REGISTER OF DEEDS  
 MACOMB COUNTY, MI

C. Description of monument for corner and accessories established to perpetuate locating the position of SET MACOMB COUNTY REMONUMENTATION MARKER AND CAP #25826 IN EXIST. MON. BOX. WITNESSES

- FND PK SW FACE UTILITY POLE, N45W, 72.95
- FND MDOT N&T IN SE FACE UTILITY POLE, N38E, 64.84
- FND "X" NW BOLT MARATHON SIGN, S43E, 103.53
- SET N&T PK & MC TAG IN W FACE G. POLE, S15W, 59.91
- FND MDOT N&T SW FACE UTILITY POLE, N25W, 66.65

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff

Date 12-9-93

Surveyor's Michigan License No. 25826

