

**SURVEY &  
REMONUMENTATION**

APR 28 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

C126171

94 SEP 30 AM 9:01

For corners in

Macomb  
(County)

Located In: Shelby Township Corner Code #

- |                                    |   |    |   |     |     |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey              | T | 3N | R | 12E | L-1 |
|                                    | T |    | R |     |     |
|                                    | T |    | R |     |     |
|                                    | T |    | R |     |     |
| 2. Property Controlling in Section | S |    | T | R   |     |
|                                    | S |    | T | R   |     |
| 3. Miscellaneous Property in Sec.  | S |    | T | R   |     |
|                                    | S |    | T | R   |     |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

CARROLL BAUGH  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

LIBR 064640484

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on July 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Glo Notes - No post set No bearing trees

- 1.) 1972-Avey, P.S. #15396; Survey L.2288, Pg.68 - Fnd 1/2" Bar in a Monument Box
- 2.) 1973-Kobs, P.S. #14097; Survey L.2370, Pg.382 - Fnd 5/8" Iron in a Monument Box
- 3.) 1979-Kobs, P.S. #14097; Survey L.2943 Pg.69 - Fnd 5/8" Iron Bar in a Monument Box, used same wit as survey 1973
- 4.) 1985-Kobs, P.S. #14097; Survey L.3880, Pg.57 - Fnd 1/2" Iron Bar in a Monument Box, used same wit as survey 1973
- 5.) 1990-Kobs, P.S. #14097; Survey L.4924, Pg.700 - Fnd 5/8" Iron Bar in a Monument Box, used same wit as survey 1973

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a Monument Box 1.5' South of the centerline of 26 Mile Road, which has a bituminous surface. This corner is now being used and accepted as a common corner with the South 1/4 corner of Section 36, T4N, R12E.

Witnesses from Survey #1, 2 & 5 were used to recover and verify the location of the found 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a Monument Box.

FIELD MEASUREMENT BETWEEN

L-1 to K-1 2660.38 Feet  
L-1 to M-1 2585.18 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON AUGUST 16, 1994.

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 I found a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in an existing Monument Box.  
N75°E 183.61' Fnd PK & Remon. Washer South face Power Pole  
S85°E 186.50' Fnd PK & Remon. Washer North face Power Pole  
S03°W 34.12' Fnd PK & Remon. Washer East face Power Pole  
S78°W 152.09' Fnd PK & Remon. Washer North face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the

Signed by Huston K. Kennedy Date Aug 22, 1994  
Surveyor's Michigan License No. 17623

